

MAR 09 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A., 1970

For corners in

MONROE (58)
(County)

Located In:

Corner Code #

WHITEFORD TWP.

- | | | | |
|---------------------------------------|-----|-----|-----|
| 1. Public Land Survey | T8S | R6E | F-6 |
| 2. Property Controlling in Section | S | T | R |
| 3. Miscellaneous Property in Sec. | S | T | R |
| 4. Lot No. _____, Recorded Plat _____ | S | T | R |
| 5. Private Claims _____ | S | T | R |

RECEIVED FOR RECORD
99 AUG -2 AM 10:37
Kevin Allen
REGISTER OF DEEDS
MONROE COUNTY, MICH

1998 & 1999 G.B. Warnke Private Remonumentation Corner

I, George B. Warnke, Jr., in a field survey on 1998 - 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and / or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 11/1975 - Case & Fleck survey #19150 - fd ctr (material not noted) - 2 witnesses which are the same as 1978 Case & Fleck
- 7/1978 - Case & Fleck survey #20216 - Fd iron - witnesses:
East 161.48' nail P. pole
N40°W 36.3 nail T. pole
- 1/1991 - G.B. Warnke LCRC, Liber 3, Page 165 (ref. 91-0120) - found iron pin per Fleck survey #20216, dated July 1978 & witnesses match 98-0028
- 1/1992 - G.B. Warnke survey 91-120 recorded in Liber 1343, Page 0477 - iron pin found - witnesses match 98-0028
- 1998 - G.B. Warnke survey #98-0028 recorded in Liber 1699, Page 0396 - found iron pin - witnesses:
N35°W 34.43' shiner in south face telephone pole
N50°W 22.47' shiner south face 6" tree
W 32.91' found capped iron
N35°E 42.87' south face steel mail box post

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner in Turk Road (tar & chip)
12/14/1998 - found 1/4" x 16" pin at surface leaning slightly west near northwest corner of 0.6' x 0.6' limestone. Top of stone could have been broke off as limestone was into stone base about 3 inches but was still solid. Used 1/4" pin at base.

RATIFIED BY PEER GROUP, PA 345 OF 1990, MONROE COUNTY, MICHIGAN, DATE 8/18/1998, COUNTY REP. *[Signature]*

REMONUMENTATION: Set 1" x 36" pipe with brass remonumentation cap in monument box to replace pin (& stone).

This position was not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set 1" x 36" pipe with brass remonumentation cap in monument box & Witnesses:
- West 19.28 feet to southeast corner of 10 inch square x 5 foot concrete post
- North 85° West 47.93 feet to set nail & remon. shiner in south face of new electric pole
- East 160.62 feet to set nail & remon. shiner in north face of new electric pole
- North 25° East 42.87 feet to southwest face of 4" steel mail box post - residence #9371
- North 30° West 34.48 feet to found double head nail & shiner in southerly face of telephone pole

Signed by *[Signature]*
Surveyor's Michigan License No. 19474

Date May 14, 1999

