

RATIFIED BY PEER GROUP  
PA 345 OF 1990  
MONROE COUNTY, MICHIGAN

date: 9/20/94

County Rep.: [Signature]  
For corners in  
Monroe (58)

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORDS  
95 DEC 28 AM 9:08  
REGISTER OF DEEDS

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)

1. Public Land Survey T \_\_\_\_\_ R \_\_\_\_\_  
Whiteford Twp. T BSB \_\_\_\_\_ 6E \_\_\_\_\_ G-4 \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_ SURVEY &  
T \_\_\_\_\_ R \_\_\_\_\_ REMONUMENTATION  
2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

APR 04 1996

Register of Deeds Stamp & File Number

COMMISSION

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

George B. Warnke, Jr. Corner

I, G.B. WARNKE, JR., in a field survey on 1994 & 1995, 19 \_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L
2	5	5	4	3	2						
3											
4	7	8	9	10	11						
5											
6	18	17	16	15	14						
7											
8	19	20	21	22	23						
9											
10	30	29	28	27	26						
11											
12	31	32	33	34	35						
13											

A. Description of original monument and accessories and/or subsequent restoration:

1/4 Section Corner Common to Sections 9 & 10 ( U.S. 223 & Sylvania Petersburg Roads - hard surface )  
1820, G.L.O. Surveyor, Joseph Wampler, between Sections 9 & 10, set qtr. sec. post & witnesses: Elm 9 S23°E 31 links & R. Oak 11 S78°W 49 links. 1965, M.S.H.D. survey chief, Jesse M. Carlson, found 3/4" pipe, 1 1/2' below road raised with 1 1/4" pipe. (Note - 1966 plans show construction centerline to be 15.93' north.) 1971, A.J. Marino notes F.I. and witnesses same as M.S.H.D. 1972, Kenneth Suydam recorded LCRC, L. 1, Pg. 233, to 1 1/4" iron pipe. 1972, G.B. Warnke found 1 1/2" iron pipe. 1975, M.D.S.H. & T. survey chief, Max W. Walter recorded L.C.R.C., L. 2, Pg. 1 & 2, found 3/4" iron pipe at level with Bit. surface. G.B. Warnke: 1978 - found iron pin in monument box and witnessed monument box in centerline of pavement N.10°W. 16.95 feet; 1989 - found iron pin in monument box and notes monument box in centerline 15.95' north & 6.16' west; 1992 - recorded L.C.R.C., L. 3, Pg. 232, to found iron pin in monument box.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

G-4 - 8/3/1994, found 1/2 inch iron pin (flared top) in monument box and witnessed as shown below.  
9/20/94 - corner was Peer Group approved. 9/28/95 - set yellow plastic remonumentation cap on found pin.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-4 - Found iron pin in monument box and set yellow plastic remonumentation cap on pin and is accepted as the best available evidence of the position of the original corner and witnesses:  
North 30° West 114.07 feet to nail/shiner in east face of electric pole  
North 30° East 94.20 feet to nail/shiner in west face of guy pole  
South 40° West 66.25 feet 16# nail in east face of electric pole  
North 3.7 feet to south edge of concrete pavement  
North 20° West 16.93 feet to monument box for centerline control of U.S. 223



Signed by [Signature] Date 12/19/1995  
Surveyor's Michigan License No. 19474

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, REVISED MAY 14, REVISED JAN.,