

**FEB 13 1998**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A., 1970**

RECEIVED FOR RECORD  
97 DEC 30 PM 3:09  
*Kevin Allen*  
REGISTER OF DEEDS  
MONROE COUNTY, MICH

For corners in

Monroe  
(County)

Located In:

Corner Code #

	<b>Whiteford</b>	
1. Public Land Survey	T <u>8</u> R <u>6</u>	<u>G-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Scott A. Warnke / M.C.R.C., in a field survey on July, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and / or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

Monroe County Road Commission Corner

A. Description of original monument and accessories and/or subsequent restoration:

- 1820 Wampler set wood post in marsh. No bearing trees.
- 1981 A.J. Marino found R.R. spike.
- 1987 G.B. Warnke found R.R. spike.
- 1991 J.C. Andrus found R.R. spike.
- 1994 Dave Andrus found R.R. spike recorded in L.C.R.C.- liber 3, page 347.
  - N5°W, 314.94' to nail/shiner in east face of Telephone pole.
  - N25°W, 67.27' to nail/shiner in east face of Telephone pole.
  - S08°W, 203.41' to nail/shiner in west face of Telephone pole.
  - N30°E, 32.70' to 5/8" x 30" iron rebar set in easterly shoulder of road 5" below grade.
  - North, 5.96' to concrete nail.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

July 1997, found R.R. spike which fit 1994 Andrus survey. Excavated a 3'x3'x3' deep hole. Found a small limestone 0.42' West of spike and found a 3" square and 4" square wood post +/- 12" long laying down East of the Spike. Evidence was not sufficient to move location. Set 1" x 36" iron pipe with brass remonumentation disk inside monument box at location of R.R. spike.

Excavated at location of concrete nail but found no evidence under nail.

RATIFIED BY PEER GROUP, P.A. 345 OF 1990, MONROE COUNTY, MICHIGAN; COUNTY REP.: [Signature], DATE 7/22/97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1" x 36" Iron pipe with brass remonumentation disk in monument box.
- Witnesses: N30°W, 98.42' to nail / M.C.R.C. tag in west face of 8" double tree.
- N35°W, 67.31' to nail / tag in East side of power pole.
- S20°W, 203.40' to nail / tag in West side of power pole.
- N30°E, 32.70' to 5/8" Iron rebar in East shoulder of Sylvania-Petersburg Road 8" below grade.

Signed by Scott A. Warnke

Date 12-10-97

Surveyor's Michigan License No. 41913

