

**SURVEY & REMONUMENTATION**

**FEB 13 1998**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A., 1970**

For corners in

<u>Monroe</u> (County)	Located In:	Corner Code #
	<b>Whiteford</b>	
1. Public Land Survey	T 8 R 6	<u>G-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD  
 97 DEC 30 PM 3:11  
*Ken Allen*  
 REGISTER OF DEEDS  
 MONROE COUNTY, MICH.

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Scott A. Warnke, in a field survey on July, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and / or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

Monroe County Road Commission Corner

A. Description of original monument and accessories and/or subsequent restoration:

- 1820 Wampler set wood post. No Bearing trees.
- November 1978 Werner Sommer set P.K. nail and disk. L.C.R.C. liber 2, page 342.
  - N40°W, 118.90' to NE corner of house.
  - S45°W, 146.95' to NE corner of house.
  - N60°W, 14.30' to NE corner of bridge rail.
  - S45°W, 16.36' to SE corner of bridge rail.
  - N60°E, 13.45' to NW corner of bridge rail.
  - S50°E, 14.97' to SW corner of bridge rail.
- 1981 A.J. Marino found P.K. nail and washer.
- 1987 G.B. Warnke set a nail over a nail using L.C.R.C. recorded in liber 2, page 342.
- 1991 J.C. Andrus found P.K. nail.
- 1994 Dave Andrus found concrete nail. Witnesses same as L.C.R.C. liber 2, page 342.
- July 1996 M.C.R.C. found nail / shiner at centerline of bridge over county drain. Appears to be in same location as set by Werner Sommer in 1978, L.C.R.C. liber 2 page 342.
  - Witnesses: N10°W, 175.95' to nail/MCRC tag in West face of Telephone pole.
  - N40°W, 118.82' to Northeast corner of Hse #7825 brick face of garage.
  - N80°W, 81.70' to Southeast corner of brick Hse #7825.
  - S45°W, 147.02' to Northeast corner of brick Hse #7807 garage.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Road was paved in July of 1997. Set 1/2" iron rebar with brass remon disk flush with road, using witnesses from July 1996. Can not set monument box because corner is located on bridge deck.

RATIFIED BY PEER GROUP, P.A. 345 OF 1990, MONROE COUNTY, MICHIGAN; COUNTY REP. *[Signature]*, DATE 7/22/97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set 1/2" iron rebar with brass remon. disk
- Witnesses: N10°W, 175.95' to nail/MCRC tag in West face of Telephone pole.
- N40°W, 118.82' to Northeast corner of Hse #7825 brick face of garage.
- N80°W, 81.70' to Southeast corner of brick Hse #7825.
- S45°W, 147.02' to Northeast corner of brick Hse #7807 garage.

Signed by *Scott A. Warnke*

Date 12-10-97

Surveyor's Michigan License No. 41913

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6		5		4		3		2		1
3											
4	7		8		9		10		11		12
5											
6	18		17		16		15		14		13
7											
8	19		20		21		22		23		24
9											
10	30		29		28		27		26		25
11											
12	31		32		33		34		35		36
13											

