

**SURVEY & REMONUMENTATION**

**FEB 13 1998**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A., 1970**

For corners in

Monroe  
(County)

Located In:

Corner Code #

1. Public Land Survey

**Whiteford**

T 8S R 6E

G-11

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

RECEIVED FOR RECORD  
 97 DEC 30 PM 3: 07  
*David Allen*  
 REGISTER OF DEEDS  
 MONROE COUNTY, MICH

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

1997 G.B. Warnke Private Remonumentation Corner

I, George B. Warnke, Jr., in a field survey on February 11, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and / or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

A. Description of original monument and accessories and/or subsequent restoration:

- G-11, T8S, R6E, Section corner to Sections 27, 28, 33 & 34 (on Sylvania-Petersburg and Sterns Roads, being hard surface) 1820, GLO Surveyor, Joseph Wampler, set post corner Secs. 27, 28, 33 & 34 in which an Aspen 18 in. dia. bears North 1.92 lks. dis & an Aspen 17 in. dia. bears N40W 1.78 lks. dis.
- 1978, George Warnke survey (#78-260) notes found nail - set boat spike - no witnesses.  
Werner Sommer LCRC, recorded in Liber 2, Page 342, shows found boat spike used by George Warnke - witnesses:  
Found PK nail & disc Tel. pole N 30° W 43.90' / Found PK nail & disc Elec. pole N 45° W 46.15' / Nail & disc in guy pole S 40° W 39.75' / Nail & disc in guy pole S 15° W 57.80'
- 1987, George Warnke survey (#87-494) notes found boat spike - uses witnesses from Werner Sommer LCRC, L.2, P. 342
- 1995, Monroe County Road Commission crew field notes show Fnd Boat Spike
- 1996, George Warnke survey (#96-0147) notes Found 3/4" Square Bolt
- 1997, George Warnke survey (#78-260) notes Found Boat Spike & references LCRC, L.2, P. 342

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

2/11/1997, G.B. Warnke found boat spike - checked with witnesses per Werner Sommer LCRC, Liber 2, Page 342

**RATIFIED BY PEER GROUP, PA 345 OF 1990, MONROE COUNTY, MICHIGAN, DATE 8/26/1997, COUNTY REP.** *[Signature]*

10/9/1997, Set 1" x 36" iron pipe with brass remonumentation cap in monument box to replace found boat spike.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1" x 36" iron pipe with brass remonumentation cap in monument box to replace found boat spike and is accepted as the best available evidence of the position of the original corner. Witnesses:  
 North 30° West 43.90 feet - Found PK nail & disc in telephone pole  
 North 45° West 46.15 feet - Found PK nail & disc in electric pole  
 South 40° West 39.75 feet - Found nail & disc in guy pole  
 South 15° West 57.80 feet - Found nail & disc in guy pole

Signed by *[Signature]*  
 Surveyor's Michigan License No. 19474

Date December 8, 1997



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 197  
 REVISED MAY 14, 197  
 REVISED JAN., 198  
 REVISED OCT., 198