

RATIFIED BY PEER GROUP  
PA 345 OF 1990  
MONROE COUNTY, MICHIGAN

date: 9/20/94

County Rep.: ASB

For corners in  
Monroe (58)

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD  
95 OCT 28 AM 9:08  
REGISTER OF DEEDS  
MONROE COUNTY, MICH

	Located In:	Corner Code #:
1. Public Land Survey Whiteford Twp.	T <u>BS</u> R <u>6E</u>	<u>H-4</u>
	T <u>   </u> R <u>   </u>	<u>SURVEY &amp;</u>
	T <u>   </u> R <u>   </u>	<u>REMONUMENTATION</u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>APR 04 1996</u>
4. Lot No. _____, Recorded Plat _____		<u>COMMISSION</u>
5. Private Claims _____		

Register of Deeds Stamp & File Number

George B. Warnke, Jr. Corner

I, G.B. WARNKE, JR., in a field survey on 1994 & 1995, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Center Section Corner to Section 10 ( on US 223 - hard surface )  
Center of Section not set by G.L.O. 1965, M.S.H.D. survey chief, Jesse M. Carlson, found stone 12 inch x 18 inch x 6 inch with chiseled "x" and raised with 1 inch conduit. 1971, A.J. Marino found PK nail and notes found PK nail 5.96 on construction centerline. 1972, G.B. Warnke survey, recorded in Liber 631, Page 536, notes found I.P. 0.2 feet below surface. 1973, Kenneth Suydam found iron. 1978 & 1989, G.B. Warnke found I. pin in monument box; and, 1992, recorded L.C.R.C., Liber 3, Page 233 to same.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-4 - 8/3/1994, found 1/2 inch iron pin (flare top) in monument box and witnessed as shown below.  
9/20/94 - corner was Peer Group approved. 9/28/95 - set yellow plastic remonumentation cap on found pin.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-4 - Found 1/2 inch iron pin (flare top) in monument box with set yellow plastic remonumentation cap on pin. This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner. Witnesses:  
South 20° East 68.73 feet to nail/shiner in west face of electric pole  
South 35° West 175.70 feet to nail/shiner in west face of electric pole  
South 6.06 feet to south edge of concrete pavement  
North 17.9 feet to north edge of concrete pavement

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Signed by [Signature]  
Surveyor's Michigan License No. 19474

Date 12/19/1995

