

SURVEY & REMONUMENTATION

FEB 13 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A., 1970

For corners in

Monroe (58)
(County)

Located In:

Corner Code #

WHITEFORD TWP.

1. Public Land Survey

T8S R6E 1-4

2. Property Controlling
in Section

S T R

3. Miscellaneous
Property in Sec.

S T R

RECEIVED FOR RECORD
 97 DEC 30 PM 3:16
George B. Warnke
 REGISTER OF DEEDS
 MONROE COUNTY, MICH.

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

1997 Remonumentation Program Corner

I, George B. Warnke, Jr., in a field survey on October, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and / or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|---|----|---|---|----|---|----|---|----|---|----|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | | 5 | | | 4 | | 3 | | 2 | | 1 |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | | 8 | | | 9 | | 10 | ● | 11 | | 12 |
| 5 | | | | | | | | | | | | | |
| 6 | 13 | | | 17 | | | 16 | | 15 | | 14 | | 15 |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | | 20 | | | 21 | | 22 | | 23 | | 24 |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | | 29 | | | 28 | | 27 | | 26 | | 25 |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | | 32 | | | 33 | | 34 | | 35 | | 36 |
| 13 | | | | | | | | | | | | | |

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1820 GLO, Surveyor - J. Wampler, set the 1/2 mile post from which an Elm 11 ins. dia. bears S73W 14 lks. dis. & a W. Oak 23 ins. dia. bears N18E 20 lks. dis.
- 1964 Michigan State Highway Department Witness Card notes Found boat spike in Mon Box & witnesses: N70W 57.14' to a C.B. & S75W 86.32' to a C.B.
- 1965 Michigan State Highway Department Witness Card notes Found boat spike in monument box & witnesses: S80W 87.75' chiseled X on top of catch basin curb / N76W 58.45' chiseled X on top of catch basin curb
- 1973 M. Freels Survey #73-109, recorded in Liber 643, Page 124, notes ships spike in mon box fd as per State Highway plans
- 1989 G.B. Warnke Survey #89-209 notes found boat spike in monument box & witnesses: N 2.48' of CL conc. pavement / N78W 57.13' to SE cor curb inlet / S79W 86.33' to NE cor curb inlet
- 1994 G.B. Warnke Survey #76-200 notes found boat spike in monument box / probed 1 3/4' to 2' below boat spike with no other evidence found - witnesses: South 2.45' centerline conc. pavement / S85E 101.68' "+" in 82+00 on S side of conc / N75W 76.45' NE cor of N conc rail for bridge over US 23 / S70W 86.40' NE cor of steel rim at SE cor bridge over US 23

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

October 7, 1997, G.B. Warnke crew found boat spike 10" deep near southeast edge of existing monument box in concrete pavement of old M-151 being 2 1/2' north of CL concrete pavement & 90' +/- east of east end of bridge and witnesses checked to previous work.

RATIFIED BY PEER GROUP, PA 345 OF 1990, MONROE COUNTY, MICHIGAN, DATE 10/4/1997, COUNTY REP. *[Signature]*

12/1/1997, G.B. Warnke wired on plastic remonumentation cap to found boat spike in existing monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Wired on plastic remonumentation cap to found boat spike in existing monument box and is accepted as the best available evidence of the position of the original corner. Witnesses:
- North 78° West 56.86 feet to southeast corner of catch basin at east end of overpass over US 23
- South 79° West 86.33 feet to northeast corner of catch basin at east end of overpass over US 23
- North 9.5 feet to north edge of concrete pavement
- South 14.5 feet to south edge of concrete pavement
- South 45° West 28.26 feet to found PK nail in center of an aerial target
- South 10° West 29.24 feet to cut "+" in north edge of top I-beam support for south guard rail
- North 05° East 18.71 feet to cut "+" in south edge of top I-beam support for north guard rail

Signed by _____

[Signature]

Date December 3, 1997

Surveyor's Michigan License No. _____

19474



APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 19
REVISED MAY 14, 19
REVISED JAN., 19
REVISED OCT., 19