

SURVEY & REMONUMENTATION

FEB 13 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A., 1970

For corners in

Monroe (58)
(County)

Located In:

Corner Code #

WHITEFORD TWP.

1. Public Land Survey

TBS R6E

J-4

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

Handwritten Signature
REGISTER OF DEEDS
MONROE COUNTY, MICH

RECEIVED FOR RECORD
97 DEC 30 PM 3:17

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

1997 Remonumentation Program Corner

I, George B. Warnke, Jr., in a field survey on October, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and / or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. did not establish center of section.

1964 Michigan State Highway Department Witness Card notes found 3/4" pipe - witnesses: N50W 46.47' to a 27" Map. / S65W 42.75' to culvert H.W. / S05W 55.83' to a 11" B. Elder / N45E 67.78' to a 18" Walnut

1965 Michigan State Highway Department Witness Card notes boat spike in monument box - witnesses: N44W 28" Maple 46.76' / N49E 18" Walnut 68.42'

1965 Michigan State Highway Department Witness Card notes found boat spike in monument box - witnesses: N45W 47.86' 29" Map / N42E 68.41' 19" Walnut / S06W 28.75' Chiseled X in W end of 12" conc. pipe cul.

1973 Meridith Freels Survey #73-109, recorded in Liber 643, Page 124, notes iron pin in mon. box fd as per State Highway plans.

1993 G.B. Warnke LCRC, Liber 3, Page 298, notes 3/4" iron pin in monument box with most witnesses as shown in Section C

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

10/7/1997, G.B. Warnke crew found boat spike in concrete in existing monument box in concrete pavement of St. Anthony Road (M-151) and checked previous witnesses.

RATIFIED BY PEER GROUP, PA 345 OF 1990, MONROE COUNTY, MICHIGAN, DATE 10/14/1997, COUNTY REP. *[Signature]*

12/1/1997, G.B. Warnke wired on plastic remonumentation cap to found boat spike in existing monument box

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Wired on plastic remonumentation cap to found boat spike in existing monument box. This position was not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner. Witnesses:

South 48.26' to found nail in north face of electric pole

North 50° East 60.15 feet to found R.R. spike in south face of telephone pole

North 25° East 95.00 feet to southeast corner of siding on Res'd #5464

South 75° East 61.25 feet to "+" in station 107+00

South 11.2 feet to south edge of concrete pavement

North 70° East 95.1 feet to nail & shiner in a Catalpa tree

Signed by *[Signature]*
Surveyor's Michigan License No. 19474



Date December 3, 1997

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													