

# SURVEY & REMONUMENTATION

FEB 13 1998

## SECTION

### LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A., 1970

For corners in

Monroe (58)

(County)

Located In:

Corner Code #

**WHITEFORD TWP.**

T8S R6E

J-6

T R

T R

T R

S T R

S T R

S T R

S T R

1. Public Land Survey

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

#### 1997 G.B. Warnke Private Corner

I, George B. Warnke, Jr., in a field survey on September 19, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and / or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- GLO did not set Center of Section
- 1974 G.B. Warnke surveys note Found I. Pin & Iron Pin
- 1988 G.B. Warnke survey notes Found Iron Pin
- 1992 G.B. Warnke survey notes Iron Pin
- 1995 G.B. Warnke surveys note Iron Pin

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

In 1997, G.B. Warnke found 1/2" pipe inside 4" steel pipe. Probed area with no other evidence found. All calculation by D. Andrus & G.B. Warnke indicate that present monumentation fits earlier corner monumentation.

RATIFIED BY PEER GROUP, PA 345 OF 1990, MONROE COUNTY, MICHIGAN, DATE 11/18/1997, COUNTY REP. [Signature]

12/1/1997 set brass remonumentation cap on found 1/2" pipe inside 4" steel pipe.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set brass remonumentation cap on found 1/2" pipe inside 4" steel pipe. This position was not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner. Witnesses:  
S5W 20.95' to set nail & shiner in east face of 10" Ash  
East 18.00' to set nail & shiner in west face of 24" Oak  
North 11.60' to set nail & shiner in south face of 18" Sassafras  
N55W 20.20' to set nail & shiner in east face of 18" Hickory

Signed by

[Signature]

Date 12/3/1997

Surveyor's Michigan License No. 19474



RECEIVED FOR RECORD  
 97 DEC 30 PM 3: 22  
 REGISTER OF DEEDS  
 MONROE COUNTY, MICH.  
 [Signature]

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2			
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													