

SURVEY & REMONUMENTATION

APR 28 1995

RATIFIED BY PEER GROUP
PA 345 OF 1990
MONROE COUNTY, MICHIGAN

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

date: 8/9/1994
County Rep.: [Signature]
For corners in

MONROE
(County)

Located In: _____ Corner Code -## _____

WHITEFORD TWP.

- | | | | | | | | |
|------------------------------------|---|---|---|---|---|---|-----|
| 1. Public Land Survey | T | 8 | S | R | 6 | E | K-5 |
| | T | | | R | | | |
| | T | | | R | | | |
| | T | | | R | | | |
| | T | | | R | | | |
| 2. Property Controlling in Section | S | | T | | R | | |
| | S | | T | | R | | |
| 3. Miscellaneous Property in Sec. | S | | T | | R | | |
| | S | | T | | R | | |

RECEIVED FOR RECORD
 91 NOV 23 AM 10:39
 [Signature]
 REGISTER OF DEEDS
 MONROE COUNTY, MICH

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____

5. Private Claims _____

1994 MONROE COUNTY REMONUMENTATION PROGRAM

Peer Group approved corner on 8/9/1994 per Act 345 of 1990.

I, G.B. WARNKE, JR., in a field survey on 8/22/1994, 19____ do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
K-5, T8S, R6E, Section Corner Common to Sections 11, 12, 13 & 14

(Intersection of Erie & Whiteford Roads - tarby)

1820, G.L.O. Surveyor, Joseph Wampler, set post at corner of Sections 11, 12, 13 & 14, witnesses: W.Oak 17 inch South 79° West 27 links & B.Oak 20 inch North 69° West 19 links. March 1902, Harry R. Gard, Deputy County Surveyor, notes old stone. 1972, G.B. Warnke found stone 1 foot below surface & set bolt at surface over stone. Found stone from old witness to bridge (now gone) to northwest over a drain per 1939 M.C.R.C. card. Recorded in P.A. 132, Liber 680, Page 249, January 1975, to I. bolt over stone by G.B. Warnke. Recorded in L.C.R.C., Liber 2, Page 264, May 1978, to found iron bolt over stone by G.B. Warnke. J.C. Andrus, Job No. 89-S-5477, notes iron pin (no witnesses). 1993, G.B. Warnke recorded L.C.R.C., Liber 3, Page 298, to round head bolt over stone.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-5 - 7/29/1994, Found round head bolt at surface, dug 12 inch diameter hole, found stone (no post found) 18 inches deep, removed stone and replaced 1 inch x 36 inch iron pipe in monument box and witnessed as shown below. 8/22/1994, set brass remonumentation cap on 1 inch x 36 inch iron pipe.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-5 - Set brass remonumentation cap on 1 inch x 36 inch iron pipe inside monument box and is accepted as a careful and faithful perpetuation of the position of the original corner and Witnesses:
 South 36° East 36.84 feet to found nail/shiner northeast face utility pole
 North 45° East 39.82 feet to found nail/shiner southeast face telephone pole
 North 40° West 32.35 feet to set punch hole top west end 15 inch C.M.P.
 North 45° West 37.00 feet to found nail/shiner southwest face telephone pole

Signed by [Signature] Date 8/22/1994

Surveyor's Michigan License No. 19474