

**SURVEY &  
REMONUMENTATION**

DEC 07 1994

**COMMISSION**

**RATIFIED BY PEER GROUP  
PA 345 OF 1990  
MONROE COUNTY, MICHIGAN**

date: 8/9/1994  
County Rep.: [Signature]  
For corners in

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

RECEIVED FOR RECORD  
94 OCT 12 PH 2:34

*Mari Allen*  
REGISTER OF DEEDS  
MONROE COUNTY, MICH

MONROE (County)	Located In:	Corner Code #:
	WHITEFORD TWP.	
1. Public Land Survey	T <u>8</u> S. R <u>6</u> E	<u>K-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

**1994 MONROE COUNTY REMONUMENTATION PROGRAM**

Peer Group approved corner on 8/9/1994 per Act 345 of 1990.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, G.B. WARNKE, JR., in a field survey on 8/22/1994, 19\_\_\_\_ do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
K-6, T8S, R6E, 1/4 Corner Common to Sections 13 & 14 (Whiteford Road at Piehl Road - tarby)  
G.L.O. Surveyor Joseph Wampler in 1820 set quarter section post and witnessed Hickory Birch 8 inch North 23° West 25 links and Hickory 10 inch South 38° East 30 links. Harry R. Gard, March 18-22, 1902 Survey, notes old stone. 1974, G.B. Warnke, survey recorded Liber 680, Page 249, set I. bolt over stone 1 foot deep and has used the point to present and recorded in L.C.R.C., Liber 2, Page 264, to iron bolt over stone.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
K-6 - 7/31/1994 - Found 3/4 inch x 6 inch bolt over limestone (took picture of stone) and broke stone and set 1 inch x 36 inch iron pipe inside monument box and witnessed as shown below. 8/22/94, set brass remonumentation cap on 1 inch x 36 inch iron pipe.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
K-6 - Set brass remonumentation cap on 1 inch x 36 inch iron pipe inside monument box and is accepted as a careful and faithful perpetuation of the position of the original corner and Witnesses:  
South 80° East 44.95 feet south end of 12 inch concrete culvert  
North 45° East 58.73 feet north end of 12 inch concrete culvert  
South 85° West 17.90 feet south end of 12 inch concrete culvert  
North 55° West 30.05 feet southeast face of metal road sign post, also being north post of arrow sign  
North 16.5 feet centerline of Piehl Road pavement to east

Signed by [Signature]  
Surveyor's Michigan License No. 19474

Date 8/22/1994

