

DEC 07 1994

COMMISSION

RATIFIED BY PEER GROUP
PA 345 OF 1990
MONROE COUNTY, MICHIGAN

date: 8/9/1994

County Rep.: [Signature]

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

94 OCT 12 PM 2:40

[Signature]
REGISTER OF DEEDS
MONROE COUNTY, MICH

For corners in

MONROE
(County)

Located In: Corner Code ??
WHITEFORD TWP.

- 1. Public Land Survey T 8 S R 6 E L-5
T ___ R ___
T ___ R ___
T ___ R ___
- 2. Property Controlling S ___ T ___ R ___
in Section S ___ T ___ R ___
- 3. Miscellaneous S ___ T ___ R ___
Property in Sec. S ___ T ___ R ___

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

1994 MONROE COUNTY REMONUMENTATION PROGRAM

Peer Group approved corner on 8/9/1994 per Act 345 of 1990.

I, G.B. WARNKE, JR., in a field survey on AUGUST 22, 1994, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

L-5, T8S, R6E, 1/4 Corner Common to Sections 12 & 13
(Erie Road)

G.L.O. Surveyor, Joseph Wampler in 1820 set quarter Section post at average distance in marsh, no bearing trees. 1902, Harry R. Gard survey notes set stone with no witnesses. 1974, Case & Fleck notes "T" iron, per survey recorded in Liber 663, Page 885. 1975, G.B. Warnke notes T iron. 1985, G.B. Warnke recorded in L.C.R.C., Liber 3, Page 13, to found T iron (indicated digging for stone 2 foot south of "T" iron with no success). 1975 to 1988, G.B. Warnke surveys notes found T iron.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-5 - 8/5/1994, found 2 inch long "T" iron at surface, dug 18 inch diameter hole, found stone 18 inches deep, removed stone, dug and found no further evidence. Set 1 inch x 36 inch iron pipe in monument box to replace stone. 8/22/1994, set brass remonumentation cap on 1 inch x 36 inch iron pipe.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-5 - Set brass remonumentation cap on 1 inch X 36 inch iron pipe and monument box to replace stone and is accepted as a careful and faithful perpetuation of the position of the original corner and witnesses:
North 60° East 41.62 feet to found nail/shiner in southwest face of utility pole
North 70° West 126.87 feet to found nail/shiner in southeast face of utility pole
North 30° West 94.37 feet to southeast corner of residence No. 4658 foundation
South 40° West 99.08 feet to northwest corner of residence No. 4659 foundation

Signed by [Signature] Date 8/22/1994
Surveyor's Michigan License No. 19474

