

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A., 1970

For corners in MONROE (58) Located In: WHITEFORD TWP. Corner Code # M-2
1. Public Land Survey T 8 S R 6 E
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. , Recorded Plat S T R
5. Private Claims

RECEIVED FOR RECORD
99 OCT 14 AM 9:14
Doris Allen
REGISTER OF DEEDS
MONROE COUNTY, MICH.

Register of Deeds Stamp & File Number

1998 & 1999 Remonumentation Program Corner

I, George B. Warnke, Jr., in a field survey on 1998 & 6/16/1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and / or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- Corner is NOT common to A-2, T8S, R7E
1820 - GLO - Joseph Wampler - North - On the E. Boundary of Sec. 1
40.00 - Set qr. Sec. Post
B. Oak 22 N56W 127
W. Oak 18 N88W 1.86
84.00 - to Cor. of T.'s 7 & 8 S., R.'s 6 & 7 E.
1900 - John VanDeventer - Minutes of Survey - Stone
11/1964 - M.R. Fleck @ Case & Fleck - Job #11209 - shows A-2 (8/7) & M-2 (8/6) being 94.8' apart
9/1973 - George B. Warnke, Jr. - Survey #73-84 - Liber 654, Page 841 - Fd. I. Pipe - N53°W 58.36' to nail E. face 10" Oak
N3°E 95.79' to stone @ W1/4 cor. Sec. 6, 8-7
S57°W 48.79' to nail E. face 24" Oak
1/1981 - George B. Warnke, Jr. - Survey #80-144 - Found 1/2" Iron Pipe - all 3 witnesses match 1973 GBW 73-84 witnesses
5/1983 - George B. Warnke, Jr. - Survey #83-182 recorded in Liber 921, Page 267 - Found I.P. - all 3 witnesses match 1973 GBW 73-84 witnesses

Grid table with columns A-M and rows 1-13. Cell (2,1) contains '6', (2,2) contains '5', (2,3) contains '4', (2,4) contains '3', (2,5) contains '2', (2,6) contains '1'. Cell (12,1) contains '31', (12,2) contains '32', (12,3) contains '33', (12,4) contains '34', (12,5) contains '35', (12,6) contains '36'. A circled '1' is in cell (2,6).

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner is located in field by School road between Summerfield & Secor roads in hard pavement.
12/8/1998 - George B. Warnke, Jr. visited corner & checked witnesses. 8/3/99 set 1 x 36 iron pipe with brass remonumentation cap with 1/2" pipe in the bottom. SET CARSONITE POST BY CORNER.

RATIFIED BY PEER GROUP, PA 345 OF 1990, MONROE COUNTY, MICHIGAN, DATE 12/8/1998, COUNTY REP. and is accepted as the best available evidence of the position of the original corner.

Handwritten signature of George B. Warnke, Jr.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1" x 36" pipe with brass remonumentation cap over found 1/2" pipe & Witnesses:
North 3° East 95.50' to 1" x 36" iron pipe with brass remon cap to replace stone at A-2, T8S, R7E / West 1/4 Corner Section 6
North 40° East 122.90' to set double head nail / remon shiner in southerly face of 18" Oak
North 30° West 67.55' to set double head nail / remon shiner in southwesterly face of 12" Oak
South 60° West 49.10' to set double head nail / remon shiner in northerly face of 30" Oak
North 35.5 foot to centerline of School Road

Signed by [Handwritten Signature]



Date August 12, 1999

Surveyor's Michigan License No. 19474

(8)