

# SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

RECEIVED FOR RECORD

94 DEC 29 AM 11:02

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

*Heri Allen*  
REGISTER OF DEEDS  
MONROE COUNTY, MICH

RATIFIED BY PEER GROUP  
PA 345 OF 1990  
MONROE COUNTY, MICHIGAN  
date: 11/22/1994  
County Rep.: [Signature]

For corners in  
MONROE  
(County)

Located In: WHITEFORD TOWNSHIP Corner Code #7  
T 8 S 6 E  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

1. Public Land Survey
2. Property Controlling in Section
3. Miscellaneous Property in Sec.

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

**1994 MONROE COUNTY REMONUMENTATION PROGRAM**  
Peer Group approved corner on 11/22/1994 per Act 345 of 1990.

G.B. WARNKE, JR., in a field survey on 12/15/1994, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
**M-7, T8S, R6E, Whiteford Township, Monroe County - ID No. 58 (Common to A-7, T8S, R7E)**  
**Section Corner Common to Sections 13 and 24, T8S, R6E, on East Township line & Sections 18 & 19, T8S, R7E)**  
**(Temperance Road being west of Summerfield Road - hard surface)**  
 1820, G.L.O. Surveyor, Joseph Wampler, set corner post, no bearing trees, 3 feet deep water in marsh area for M-7, T8S, R6E. 1820, G.L.O. Surveyor, Joseph Wampler, Intersect W. Boundary at post for A-7, T8S, R7E. 1902, Harry Gard, County Survey Book 3, found old stone, no witness trees. 1960, A.J. Marino survey refers to a Case and Fleck survey, but notes no stone found. Does not mention what is at corner. 1966, Case and Fleck survey does not state monumentation. 1981, G.B. Warnke used found R.R. spike over conc. culvert (Survey No. 81-28). 1987, James C. Andrus used found existing railroad spike at Northwest corner, Northwest quarter, Section 19 (Survey No. 87S-4906).

Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
**M-7 - 11/16/1994, found magnetic reading under witnesses for railroad spike crossing concrete culvert approximately 1 foot under crossing. Did not excavate. Awaiting further instructions. 12/15/1994, set 1/2 inch x 13 inch rebar in drilled hole in cross culvert with brass remonumentation cap in monument box (culvert 18 inches deep) to replace railroad spike.**

Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
**M-7 - Set 1/2 inch x 13 inch rebar in drilled hole in cross culvert (culvert 15 inches deep) with brass remonumentation cap in monument box, to replace railroad spike, and is accepted as the best available evidence of the position of the original corner and Witnesses:**  
 South 10° East 23.87 feet to cross cut in concrete culvert  
 North 10° West 14.32 feet to cross cut in concrete culvert  
 South 50° East 66.34 feet to PK nail in south face of electric pole  
 North 15° East 57.95 feet to PK nail in east face of electric pole

igned by [Signature] Date 12/15/1994  
 Surveyor's Michigan License No. 19474

