

**SURVEY &
REMONUMENTATION**

DEC 07 1994

RATIFIED BY PEER GROUP
PA 345 OF 1990
MONROE COUNTY, MICHIGAN

date: 11-16-93

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

County Rep.: [Signature]

For corners in

MONROE
(County)

Located In: WHITEFORD TWP.
Corner Code ##

1. Public Land Survey	T	<u>8</u>	S	R	<u>6</u>	E	<u>M-11</u>
	T	_____	R	_____	_____	_____	_____
	T	_____	R	_____	_____	_____	_____
	T	_____	R	_____	_____	_____	_____
2. Property Controlling in Section	S	_____	T	_____	R	_____	_____
	S	_____	T	_____	R	_____	_____
3. Miscellaneous Property in Sec.	S	_____	T	_____	R	_____	_____
	S	_____	T	_____	R	_____	_____

RECEIVED FOR RECORD
94 OCT 12 PM 2:10
REGISTER OF DEEDS
MONROE COUNTY, MICH
[Signature]

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1993 MONROE COUNTY REMONUMENTATION PROGRAM
Peer Group approved corner on 11/16/1993 per Act 345 of 1990.

I, G.B. WARNKE, JR., in a field survey on AUGUST 22, 1994, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

M-11, T8S, R6E, Township Section Corner Common to Sections 25 & 36
(At Adler & Sterns Roads)
1820, G.L.O. Surveyor set post. Witnesses: N.30°E. 10 links to 15 inch B. Oak & S.43°E. 57 links to 8 inch B. Oak. / Surveys in area indicate that A-11, T8S, R7E is on line with this corner. / L.C.R.C., Liber 1, Page 345, notes limestone.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-11 - 10/28/93 - found small engine shaft 14 inches long over stone 16 inches deep and replaced on 8/22/94 with set 1 inch x 36 inch black iron with remonumentation cap ~~in the monument box~~ and witnessed as shown below. p. pe.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-11 - 8/22/1994 - Set 1 inch x 36 inch black iron pipe with remonumentation cap ~~in the monument box~~ to replace found small engine shaft 14 inches long over stone 16 inches deep, which is accepted as the best available evidence of the position of the original corner and Witnesses:
North 39.72' found capped iron pipe (No. 19474) A-11, T8S, R7E, Redford
South 65° West 95.95' found nail/shiner north face utility pole
South 17.40' north face of fence corner of cemetery
North 05°E 3.40' south face of fence corner of cemetery
North 45° West 1.00' M.S./H.D. witness tag in west face of broken utility pole



Signed by [Signature] Date Aug 22, 1994
Surveyor's Michigan License No. 19474