

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
MONROE

(County)

Located In:

Corner Code ~~##~~

1. Public Land Survey	T <u>85</u> R <u>8E</u>	<u>E-11</u>
	T <u>85</u> R <u>8E</u>	<u>6-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, GARY C. BILLOW, in a field survey on JULY 25, 19 90, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(E-11) CORNER ESTABLISHED IN 1827 BY GLO DEPUTY SURVEYOR ROBERT CLARK (THE U.S. DEPT. OF THE INTERIOR, BUREAU OF LAND MANAGEMENT HAS ADVISED THAT THE CLARK SURVEY, NOT THE 1820 JOSEPH WAMPLER SURVEY OF THIS TOWNSHIP IS THE OFFICIAL SURVEY). FOUND NO RECORD OF CLARK'S ACCESSORIES. CORNER SHOWN ON PLAT OF WILLOW POINT (LIBER 10 OF PLATS, PAGE 44, MONROE COUNTY RECORDS) AS A TIE. CORNER RECORDED UNDER ACT 74, P.A. 1970 BY D. HOOTH RLS #7966 IN 1975 (LCRC LIBER 2, PAGE 80) AND BY GORDON MacCAMMON IN 1988 (LCRC LIBER 3, PAGE 46).

(G-11) CORNER ESTABLISHED IN 1827 BY GLO DEPUTY SURVEYOR ROBERT CLARK (SEE NOTE ABOVE). FOUND NO RECORD OF CLARK'S ACCESSORIES. RECORDS OF MICHIGAN DEPT. OF TRANSPORTATION SHOW 1-1/2" PIPE SURROUNDED BY 3 STONES. ACCESSORIES: 1" I. PIPE S 0°45'E 239.65', 24" HAMTHORN S 0°45'E 307.15', 2713.20' TO CENTERLINE OF SUMMIT ST., 65+98.4

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E-11) FOUND AND ACCEPTED 3/4" CAPPED PIPE NOTED BY MacCAMMON. MacCAMMON RECORD ACCESSORIES CHECK. HOOTH ACCESSORIES TO T/P AND P/P CHECK. BASED ON MONUMENTATION ACCEPTED AS PERPETUATING THE PLAT OF WILLOW POINT, TIE DISTANCE FROM CORNER TO THE NW CORNER OF THE PLAT MEASURES 4234.23' (REC. AS 4235.3').

(H-11) FOUND AND ACCEPTED 3/4" PIPE INSIDE OF A 1-1/4" PIPE. MDOT ACCESSORIES WERE NOT RECOVERED. FOUND IRON IN CENTER OF MEDIAN (15' EAST OF CENTERLINE OF SOUTHBOUND LANE) OF SUMMIT STREET (HWY 24-A) IS 2712.38' WEST OF CORNER AND 0.17' SOUTH OF A LINE BETWEEN E-11 AND G-11.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E-11) FOUND 3/4" CAPPED PIPE
 N35E 35.39' FD NAIL AND SHINER IN TP
 S45W 39.56' FND NAIL AND SHINER IN PP
 N65W 76.77' FD NAIL AND SHINER IN TP
 S20E 81.83' TELEPHONE POLE

(G-11) FOUND 3/4" PIPE INSIDE 1-1/4" PIPE
 S47E 16.73' SET NAIL AND MDNR TAG IN 7" COTTONWOOD
 S73E 54.43' SET NAIL AND MDNR TAG IN 10" WILLOW
 WEST 2712.38' FND IRON IN MEDIAN OF SUMMIT ST.
 NORTH 4' WATER'S EDGE

Signed by Gary C. Bilow

Date _____

Surveyor's Michigan License No. 26453

