

# SURVEY & REMONUMENTATION

APR 28 1995

## COMMISSION

### LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RATIFIED BY PEER GROUP  
PA 345 OF 1990  
MONROE COUNTY, MICHIGAN

date: 11/8/1993  
County Rep.: [Signature]

RECEIVED FOR RECORD  
94 NOV 23 AM 10:43  
[Signature]  
REGISTER OF DEEDS  
MONROE COUNTY, MICH

For corners in

MONROE  
(County)

Located In: Corner Code -#  
BEDFORD TWP.

1. Public Land Survey	T <u>8</u> S R <u>7</u> E	A-8
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

MONROE COUNTY REMONUMENTATION PROGRAM  
Peer Group approved corner on 11/08/1993 per Act 345 of 1990.

I, G.B. WARNKE, JR., in a field survey on 8/24/1994, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

A-8, T8S, R7E, 1/4 Corner Between Section 19, T8S, R7E, & Section 24, T8S, R6E  
(At Intersection of Consear & Adler Roads) (Also M-8, T8S, R6E)  
G.L.O. Surveyor set 1/4 post on east range line of Town 8 South, Range 6 East. / Road survey in 1924 indicates a stone. / Concrete pavement in place since approximately 1929. / J.W. White survey (1920's?) indicates a stone. / Case & Fleck survey in May of 1950 indicates a spike. / G.B. Warnke surveys No. 77-42, 81-73 & 83-271 indicates a 1/2 inch iron pipe over a bolt.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-8 - 9/8/1993, found a 1/2 inch iron pipe at road surface. Warnke references fit well. 8/24/1994, dug 18 inch x 36 inch deep hole, found 1/2 inch x 3 inch iron pipe over 1 inch x 3 inch hex bolt, and probed in all directions but no stone or post found. Found 1 inch x 24 inch iron pipe approximately 12 inches below surface and 0.6 feet east of 1/2 inch x 3 inch iron pipe. Set brass remonumentation cap on 1 inch x 36 inch iron pipe inside monument box to replace 1/2 inch iron pipe over bolt. Witnessed as shown below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-8 - Brass remonumentation cap on 1 inch x 36 inch iron pipe inside monument box to replace found iron pipe over bolt and is accepted as the best available evidence of the position of the original corner and witnesses:  
South 75° West 74.54 feet to found nail/shiner in north face of telephone pole  
North 40° West 37.48 feet to found nail/shiner in south face of electric pole  
North 45° East 48.58 feet to found nail/shiner in southeast face of telephone pole  
South 50° East 47.17 feet to found nail/shiner in north face of telephone pole

Signed by [Signature]  
Surveyor's Michigan License No. 19474

Date 8/24/1994