

**SURVEY &
REMONUMENTATION**

DEC 07 1994

COMMISSION

RATIFIED BY PEER GROUP
PA 345 OF 1990
MONROE COUNTY, MICHIGAN

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

94 OCT 12 PM 2: 12

date: 10-26-93
County Rep.: [Signature]
For corners in

MONROE
(County)

Located In: BEDFORD TWP.
Corner Code ##

1. Public Land Survey	T <u>8</u> S <u>R</u> <u>7</u> E	<u>A-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Keri Allen
REGISTER OF DEEDS
MONROE COUNTY, MICH

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

MONROE COUNTY REMONUMENTATION PROGRAM Peer Group
approved corner on 10-26-1993 per Act 345 of 1990.

I, G.B. WARNKE, JR., in a field survey on August 24, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

A-11, T8S, R7E, 1/4 Corner Between Sections 30 & 31, T8S, R7E
G.L.O. Surveyor Joseph Wampler intersected the west range line 66 links north of post.
Witnesses: B. Oak 11 inch N.25°E. 33 links & B. Oak 12 inch S.43°E. 27 links. / Old book notes stone monument (Book 33, Page 45 - location unknown). Appears that B.M. Wilcox, County Surveyor, set corner in 1873. / M.R. Fleck probably found stone in April 1944. / R.E. Harrison, CE, noted "+" on survey report. / Surveys since 1972 relate to iron pin over stone and has been used to present.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-11 On 5/4/1992, found iron rod over stone and witnessed as shown below. It was revisited on 10-28-1993; I examined the area and found that A-11 was on line with the east range line of T8S, R6E, between M-11 & M-9. 8/24/1994, set brass remonumentation cap on 1 inch x 36 inch black iron pipe inside monument box to replace found rod over stone. Witnesses as shown below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set brass cap on 1" x 36" black iron pipe inside monument box to replace
A-11 - Found Iron Rod Over Stone and is accepted as the best available evidence of the position of the original corner and witnesses:
South 02°24' East 39.78' found iron rod over stone at southeast corner of Section 25, T8S, R6E, M-11
South 36.28' D.H. nail/shiner in west face of utility pole
North 15° West 122.02' D.H. nail/shiner in east face of utility pole
North 15° East 140.40' D.H. nail/shiner in west face of electric pole
South 45° West 112.65' nail/shiner in north face of utility pole

Signed by [Signature]
Surveyor's Michigan License No. 19474

Date AUGUST 24, 1994

