

**SURVEY &
REMONUMENTATION**

DEC 07 1994

COMMISSION

RATIFIED BY PEER GROUP
PA 345 OF 1990
MONROE COUNTY, MICHIGAN

date: 10-26-93
County Rep: [Signature]

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD
94 OCT 12 PM 2:14

Keri Allen
REGISTER OF DEEDS
MONROE COUNTY, MICH

For corners in

<u>MONROE</u> (County)	Located In:	Corner Code #
	BEDFORD TWP.	
1. Public Land Survey	T <u>8</u> S R <u>7</u> E	<u>C-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

MONROE COUNTY REMONUMENTATION PROGRAM Peer Group approved corner on 10-26-1993 per Act 345 of 1990.

I, G.B. WARNKE, JR., in a field survey on SEPTEMBER 2, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:
C-4, T8S, R7E, 1/4 Corner Between Sections 7 & 8 (On Secor Road [C.R. - 151])
G.L.O. Surveyor Joseph Wampler set 1/4 corner post between Sections 7 & 8 in 1820.
Witnesses: B. Oak 21 inch S.75°E. 48 links & W. Oak 17 inch N.26°W. 89 links. / A.J. Marino notes "cap" 1951. / In March of 1964, M.D.O.P. Surveyor L.J. Czubak (No. 12581) found 1 1/4 inch iron rod over stone. In October of 1965, M.D.O.P. Survey Chief Liubakka set boat spike in monument box. / This point was used until the roads were re-aligned. During this construction period, G.B. Warnke probed and dug for stone, but not found. To date, corner replaced by a 1/2 inch rebar in square monument box which is used.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
C-4 - 10/25/1993, found 1/2 inch rebar in square top monument box and witnessed as shown below. 9/2/1994, 1/2 inch rebar could not be removed. Set brass remonumentation cap on 1/2 inch rebar.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
C-4 - Found 1/2 Inch Rebar In Square Top Monument Box and is accepted as the best available evidence of the position of the original corner and witnesses:
North 80° East 89.07' southwest corner of foundation of attached garage to house No. 10160
South 85° East 32.90' P.K. nail in west face of utility pole
North 25° West 72.41' nail/shiner in east face of telephone pole
South 45° West 46.36' nail/shiner in east face of telephone pole

igned by [Signature]
urveyor's Michigan License No. 19474

Date SEPTEMBER 2, 1994

