

SURVEY & REMONUMENTATION

RATIFIED BY PEER GROUP
PA 345 OF 1990
MONROE COUNTY, MICHIGAN

APR 28 1995

date: 11/22/1994
County Rep.: [Signature]

COMMISSION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD
94 DEC 16 PM 3:29

For corners in
MONROE
(County)

Located In: BEDFORD Corner Code 44
TWP.

- | | | |
|------------------------------------|---------------------------|-------|
| 1. Public Land Survey | T <u>8</u> S R <u>7</u> E | C-5 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

[Signature]
REGISTER OF DEEDS
MONROE COUNTY, MICH

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1994 MONROE COUNTY REMONUMENTATION PROGRAM

Peer Group approved corner on 11/22/1994 per Act 345 of 1990.

I, G.B. WARNKE, JR., in a field survey on 12/2/1994, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
C-5, T8S, R7E, Bedford Township, Monroe County - ID No. 58
Section Corner Common to Sections 7, 8, 17 & 18
(Erie & Secor Roads - 4" asphalt, 6" stone, dark yellow sand)

1820, G.L.O. Surveyor, Joseph Wampler, set post Cor. of Secs. 7, 8, 17 & 18: B. Oak 13 (inch) S.5°W. 95 lks. & W. Oak 16 (inch) West 95 (links). Transcribed notes from old book indicate in 1899 VanDeventer notes stone. A.J. Marino: 1949 & undated misc. records note stone; 1951 notes set R.R. spike; 1953 & 1954 notes R.R. Spike. M.R. Fleck: 1972, 1975, 1977, 1979 & 1984 notes found R.R. Spike; 1985 notes found iron; undated witness card notes iron bar. G.B. Warnke: 1976, 1978, 1979, 1985, 1987 & 1988 notes R.R. spike.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-5 - 11/17/1994, found railroad spike 4 inches below surface. Dug an 18 inch x 30 inch hole and probed in all directions; no further evidence found by railroad spike. Compared 1951 witnesses (oldest known witnesses to railroad spike) and last known witnesses to stone and found them to be a few feet different. Dug a 12 inch x 18 inch hole, approximately 3 feet southwest of railroad spike, and probed in all directions and found dark blue granite stone approximately 3.5 feet south and 0.5 feet west of railroad spike and approximately 1 foot deep. 12/2/1994, set 1 inch x 36 inch iron pipe with brass remonumentation cap inside monument box to replace found railroad spike.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-5 - set 1 inch x 36 inch iron pipe with brass remonumentation cap inside monument box to replaced railroad spike and accepted as the best available evidence of the position of the accepted corner and
Witnesses:

- South 40° East 49.10 feet to nail/shiner in northeast face of utility pole
- South 45° West 42.16 feet to nail/shiner in north face of telephone pole
- North 45° West 42.25 feet to nail/shiner in south face of telephone pole
- North 60° East 60.75 feet to north end of 12 inch concrete culvert

Signed by [Signature] Date 12/2/1994
Surveyor's Michigan License No. 19474

