

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORDS
 91 NOV 23 AM 10:44
 REGISTER OF DEEDS
 MONROE COUNTY, MICH.

RATIFIED BY PEER GROUP
 MONROE COUNTY REGISTER OF DEEDS
 DATE: 11/16/1993
 County Rep. [Signature]
 For corners in
MONROE

Located In: **BEDFORD** Corner Code **##**
TWP.

- | | | |
|------------------------------------|---------------------------|-------|
| 1. Public Land Survey | T <u>8</u> S R <u>7</u> E | E-1 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims
1993 MONROE COUNTY REMONUMENTATION PROGRAM
 Peer Group approved corner on 11/16/1993 per Act 345 of 1990.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, G.B. WARNKE, JR., in a field survey on 9/26/1994, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-1, T8S, R7E, North Corner Common To Sections 4 & 5, T8S, R7E, & Sections 32 & 33, T7S, R7E (Douglas & Rauch Roads - asphalt over concrete) (common to E-13, T7S, R7E - approved 10/4/94)
 1820, G.L.O. Surveyor, Joseph Wampler, traveled 81.68 chains north & intersected north boundary corner between Sections 4 & 5. Witnesses: B. Oak 18 inch N.20°W. 174 links & W. Oak 9 inch N.40°E. 110 links. 1899, VanDeVenter may have found stone. 1924, Monroe County Road Commission found stone during road survey of township line (Rauch Road). 1959, A.J. Marino survey used 3/4 inch iron pipe. Surveys from 1973 to date witness 3/4 inch iron pipe.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-1 - 11/10/1993, found square head nail & washer at surface cut 6 inch x 6 inch hole and found 3/4 inch iron pipe 3 inches below pavement, hit concrete on west & north edge of pipe at 5 inches below pavement. Discontinued excavation at this time and reset square head nail & washer over pipe and witnessed as shown below. 9/26/1994, set 1 inch x 36 inch iron pipe with remonumentation cap inside monument box to replace iron pipe and nail/washer and witnessed as shown below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-1 - Set 1 inch x 36 inch iron pipe with remonumentation cap inside monument box to replace iron pipe and nail/washer & is accepted as the best available evidence of the position of the original corner & Witnesses:
 South 45° West 45.87' found nail in northeast face of utility pole
 South 45° West 46.28' found PK nail in east face of utility pole
 North 55° West 59.33' found nail in southeast face of telephone pole
 North 40° West 40.65' southeast face of gas vent pipe
 North 20° East 98.70' southwest face of 4 inch diameter gas vent pipe regulator
 North 45° East 41.69' found PK nail in northwest face of telephone pole
 South 40° East 53.11' set nail/shiner in west face of telephone pole
 North 20° East 94.97' southwest face of 2 inch diameter gas pipe on regulator

Signed by [Signature] Date 9/26/1994
 Surveyor's Michigan License No. 19474