

SURVEY & REMONUMENTATION

APR 28 1995

RATIFIED BY PEER GROUP
PA 345 OF 1990
MONROE COUNTY, MICHIGAN

date: 10/26/1993

County Rep.: _____
For corners in _____

COMMISSION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

MONROE <small>(County)</small>	Located In: BEDFORD TWP.	Corner Code # E-4
1. Public Land Survey	T <u>8</u> S R <u>7</u> E	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____
MONROE COUNTY REMONUMENTATION PROGRAM
Peer Group approved corner on 10-26-1993 per Act 345 of 1990.

I, G.B. WARNKE, JR., in a field survey on 12/6/1994, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	I
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

E-4, T8S, R7E, 1/4 Corner Between Sections 8 & 9 (On Douglas Road - hard surface)
G.L.O. surveyor Joseph Wampler set 1/4 section post. Witnesses: W. Oak 18 inch S.4°W. 124 links & B. Oak 7 inch N.39°E. 105 links. / Old book indicates stone; Surveyor unknown. / A.J. Marino in August of 1946 & 1953 indicates stone with notes. / M.R. Fleck in April of 1955 notes stone; and in December of 1965, set iron rod. / Douglas Road was paved in the early 1970's. / M.R. Fleck recorded L.C.R.C., Liber 1, Page 357, October of 1973, & L.C.R.C., Liber 2, Page 25, March of 1975, to 1/2 inch iron rod. / G.B. Warnke raised iron rod with 1/2 inch iron pipe and then an iron bolt. This corner has been used extensively from 1972 to 1977. Corner monumented by a bolt over a 1/2 inch iron pipe over an iron rod.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-4 - 9/13/1993, found chisled "+" on top of 2 inch square head bolt over a 1/2 inch iron pipe over an iron rod based on previous witnesses and re-witnessed as shown below. 12/6/1994, set 1 inch x 36 inch iron pipe with brass remonumentation cap inside monument box to replace said bolt over iron over rod.

RECEIVED FOR RECORD
54 DEC 16 PM 3:34
George B. Warnke
REGISTER OF DEEDS
MONROE COUNTY, MICH

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-4 - Set 1 inch x 36 inch iron pipe with brass remonumentation cap inside monument box to replace found chisled "+" on top of 2 inch square head bolt over a 1/2 inch iron pipe over an iron rod based on previous witnesses and re-witnessed. Point is accepted as the best available evidence of the position of the original corner and witnesses:
South 20° East 63.56 feet to set nail/shiner in west face of telephone pole
North 85° East 30.41 feet to set nail/shiner in south face of electric & telephone pole
North 70° East 100.93 feet to northwest corner of house No. 10195
North 70° West 37.62 feet to found nail/shiner in east face of electric pole
North 45° West 10.6 feet to southeast corner of concrete slab

Signed by _____ Date 12/6/1994
Surveyor's Michigan License No. 19474

