

# SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

RATIFIED BY PEER GROUP  
PA 345 OF 1990  
MONROE COUNTY, MICHIGAN

date: 11/16/1993  
County Rep: [Signature]

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD  
94 DEC 29 AM 11:07

*[Signature]*  
REGISTER OF DEEDS  
MONROE COUNTY, MICH

For corners in

MONROE  
(County)

Located In: BEDFORD Corner Code #  
TWP.

1. Public Land Survey	T <u>8</u> S R <u>7</u> E	<u>E-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_  
**1993 MONROE COUNTY REMONUMENTATION PROGRAM**  
Peer Group approved corner on 11/16/1993 per Act 345 of 1990.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9					●								
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, G.B. WARNKE, JR., in a field survey on 12/14/1994, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

E-9, T8S, R7E, Section Corner Common to Sections 20, 21, 28 & 29 (At Dean & Douglas Roads)  
1820, G.L.O. Surveyor set corner post at Sections 20, 21, 28 & 29; witnesses: B. Oak 11 (inch) S.68°W. 8 links & B. Oak 10 (inch) N.68°E. 36 links. / Witness card notes found stone in 1948 with 4 witnesses (none remain). / 1911, J.W. White survey notes stone - no witnesses. / G.B. Warnke set bolt over stone about 1975. / Rolf Goerlich, former crew chief for M.R. Fleck, stated that they used the stone. / The plats of Douglas Village 1 & 2 were from the stone. / Several surveys by G.B. Warnke have occupied this corner. / 1979, A.J. Marino survey used an i.rod 2.86 feet north of bolt over stone. This iron hasn't been found for several years.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-9 - On 10/29/1993, found 2 inch square bolt 3 1/2 inches deep and set 1/2 inch by 2 1/2 inch hex bolt with washer over found bolt and re-witnessed. 12/14/1994, set 1 inch x 36 inch iron pipe with brass remonumentation cap inside monument box to replace bolts.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-9 - set 1 inch x 36 inch iron pipe with brass remonumentation cap inside monument box to replace bolts and is accepted as the best available evidence of the position of the original corner and witnesses:  
North 45° West 45.28' found nail/shiner in east face of telephone pole  
North 45° East 45.45' found nail/shiner in northwest face of telephone pole  
South 50° West 61.74' top nut of hydrant  
South 45° East 46.25' found nail/shiner in north face of utility pole

Signed by [Signature]  
Surveyor's Michigan License No. 19474

Date 12/14/1994

