

# SURVEY & REMONUMENTATION

APR 28 1995

## COMMISSION

### LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

94 DEC 29 AM 11:08

**RATIFIED BY PEER GROUP**  
PA 345 OF 1990  
MONROE COUNTY, MICHIGAN

date: 10/24/1993

County Rep.: [Signature]

*Meri Allen*  
REGISTER OF DEEDS  
MONROE COUNTY, MICH

For corners in		Located In: BEDFORD TWP.	Corner Code #
MONROE			
(County)			
1. Public Land Survey	T <u>8</u> S R <u>7</u> E		<u>F-5</u>
	T _____ R _____		_____
	T _____ R _____		_____
	T _____ R _____		_____
2. Property Controlling in Section	S _____ T _____ R _____		_____
	S _____ T _____ R _____		_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		_____
	S _____ T _____ R _____		_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

MONROE COUNTY REMONUMENTATION PROGRAM Peer Group approved corner on 10-26-1993 per Act 345 of 1990.

G.B. WARNKE, JR., in a field survey on December 16, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
 F-5, T8S, R7E, 1/4 Corner Between Sections 9 & 16 (On Erie Road)  
 G.L.O. Surveyor Joseph Wampler set 1/4 section post. Witnesses: B. Oak 14 inch S.68°E. 44 links & B. Oak 18 inch N.8°E. 33 links. / Old book notes stone; Surveyor unknown. / A.J. Marino in 1950? notes found stone and witnessed. / M.R. Fleck in March of 1971 & April of 1953 notes found stone and witnessed. / 1972 to present notes a railroad spike at surface. / G.B. Warnke in August of 1993 excavated and found stone under railroad spike and set 1 inch iron pipe at surface.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 F-5 9/13/1993, found railroad spike at surface, referenced, pulled out, dug, and found "T" iron under west edge of spike, and found stone 20 1/2 inches deep with 1/2 inch iron rod and 1/2 inch iron pipe along west edge of stone. Left "T" iron and 1/2 inch iron pipe by stone and drove 1" x 17" capped (#19474) iron pipe over dimple in stone and witnessed as shown below. 12/16/1994, set 1 inch x 36 inch iron pipe with brass remonumentation cap in monument box to replace pipe over stone; broke stone and left pipe in whole by stone.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 Set 1 inch x 36 inch iron pipe with brass remonumentation cap in monument box to replace F-5 1" x 17" capped (#19474) iron pipe over dimple in stone (left "T" iron and 1/2 inch iron pipe by stone) and is accepted as a careful and faithful perpetuation of the position of the original corner and witnesses:  
 North 55° East 41.50' found nail/shiner in northwest face of electric & telephone pole  
 South 5° West 32.25' found nail in east face of electric pole  
 South 40° West 83.59' set nail/shiner in northwest face of electric pole  
 North 10° West 132.35' southeast corner of attached garage of house No. 2074  
 North 80° West 27.86' set chisled "+" in concrete drive near southeastly end

Signed by [Signature] Date 12/16/1994  
 Surveyor's Michigan License No. 19474

