

SURVEY & REMONUMENTATION

RATIFIED BY PEER GROUP
PA 345 OF 1990

APR 28 1995

MONROE COUNTY, MICHIGAN

date: 10-24-1993

COMMISSION
LAND CORNER RECORDATION CERTIFICATE

County Rep.: [Signature]
For corners in

Filing Requirement of Act 74, Mich. P.A. 1970

<u>MONROE</u> (County)	Located In: <u>BEDFORD</u> TWP.	Corner Code <u>##</u> <u>G-2</u>
1. Public Land Survey	T <u>8 S</u> R <u>7 E</u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

MONROE COUNTY REMONUMENTATION PROGRAM Peer Group
approved corner on 10-26-1993 per Act 345 of 1990.

I, G.B. WARNKE, JR., in a field survey on NOVEMBER, 1994,
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2							
3												
4	7	8	9	10	11							
5												
6	18	17	16	15	14							
7												
8	19	20	21	22	23							
9												
10	30	29	28	27	26							
11												
12	31	32	33	34	35							
13												

A. Description of original monument and accessories and/or subsequent restoration:

G-2, T8S, R7E, 1/4 Corner Between Sections 3 & 4 (Jackman Road between Rauch & M-151)
G.L.O. Surveyor Joseph Wampler set 1/4 section post between Sections 3 & 4. Witnesses:
B. Oak 40 inch N.62°W. 24 links, B. Oak 17 inch N.65°E. 90 links. / Old book indicates
stone at 1/4 corner between Section 3 & 4, (Jackman Road). The Northeast 1/4 of Section 4
was measured by John W. VanDeventer in 1900. / Surveys by M.R. Fleck in 1970's witness a
5/8 inch iron rod. / This corner was excavated following chip and seal paving in 1991 and
found intact. This corner has been used extensively for this area.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-2 - 9/17/1993, found mangled 5/8 inch iron pipe (3/8 inch interior diameter) and
witnessed as shown below.

11/1994, set 1 inch x 36 inch iron pipe with brass remonumentation cap
inside monument box to replace found pipe.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-2 - 9/17/1993, found mangled 5/8 inch iron pipe (3/8 inch interior diameter). Point is
accepted as the best available evidence of the position of the original corner. Witnesses:
South 45° East 25.41' nail/shiner in northwest side of power pole
North 70° East 37.24' nail/shiner in northwest side of 24 inch Maple tree
South 50° West 44.19' nail/shiner in southeast side of 48 inch Oak tree
West 59.72' nail/shiner in northeast side of Poplar tree
West 33.00' capped (No. 19474) iron pipe on East & West 1/4 line

11/1994, set 1 inch x 36 inch iron pipe with brass remonumentation cap
inside monument box to replace found pipe.

Signed by [Signature] Date NOVEMBER 28, 1994
Surveyor's Michigan License No. 19474

REGISTER OF DEEDS
MONROE COUNTY, MICH.
94 DEC 16 PM 3:35