

REMONUMENTATION

APR 28 1995

RATIFIED BY PEER GROUP
PA 345 OF 1990
MONROE COUNTY, MICHIGAN

COMMISSION

date: 10/26/1993
County Rep.: [Signature]
For corners in

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

<u>MONROE</u> (County)	Located In: <u>BEDFORD</u>	Corner Code =#
	<u>TWP.</u>	
1. Public Land Survey	T <u>8</u> S R <u>7</u> E	<u>G-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

MONROE COUNTY REMONUMENTATION PROGRAM Peer Group
approved corner on 10-26-1993 per Act 345 of 1990.

I, G.B. WARNKE, JR., in a field survey on December 4, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2						
3											
4	7	8	9	10	11						
5											
6	18	17	16	15	14						
7											
8	19	20	21	22	23						
9											
10	30	29	28	27	26						
11											
12	31	32	33	34	35						
13											

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-4, T8S, R7E, 1/4 Corner Common To Sections 9 & 10 (On Jackman Road)
G.L.O: Surveyor Joseph Wampler set 1/4 section post in pond. Witnesses: B. Oak 18 inch South 600 links & no other bearing trees. / Old records not found. / A.J. Marino notes pipe set beside stone and witnessed, date unknown, 1950's?. No survey found. / Sheridan in 1992, Case & Fleck in 1986, and Warnke in 1988 used iron pipe.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-4 - 9/13/1993, Found 1/2 inch iron pipe at surface, referenced, dug 12 inch hole and found stone 20 inches deep with another 1/2 inch iron pipe leaning east over west edge of stone. Set 1/2 inch x 20 inch capped (No. 19474) iron pipe over stone and is accepted as a careful and faithful perpetuation of the position of the original corner and witnessed as shown below.

12/4/1994, set 1 inch x 36 inch iron pipe with brass remonumentation cap inside monument box to replace pipe over stone.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-4 - Set 1/2 inch x 20 inch capped (No. 19474) iron pipe over stone and is accepted as a careful and faithful perpetuation of the position of the original corner and witnesses:
South 20° East 79.25' found railroad spike in west face of telephone pole
South 25° East 40.38' found chisled "x" on top of east end of elliptical concrete culvert
South 60° West 22.45' found chisled "x" on top of west end of elliptical concrete culvert
North 75° West 34.19' found nail/shiner in north face of electric pole
North 65° West 131.21' southeast corner of brick house No. 10205

12/4/1994, set 1 inch x 36 inch iron pipe with brass remonumentation cap inside monument box to replace pipe over stone.

Signed by [Signature]
Surveyor's Michigan License No. 19474

Date December 4, 1994

94 DEC 16 PM 3:36

REGISTER OF DEEDS
MONROE COUNTY, MICH

STATE OF MICHIGAN
GEORGE B. WARNKE, JR.
LAND SURVEYOR
NO. _____
REVISOR

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 1985
REVISED MAY 1987