

REMONUMENTATION

APR 28 1995

RATIFIED BY PEER GROUP
PA 345 OF 1990
MONROE COUNTY, MICHIGAN

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

94 DEC 29 AM 11:09

date: 11/16/1993

For Corner #4a. [Signature]

MONROE
(County)

Located in: BEDFORD TWP. Corner Code #H-3

- 1. Public Land Survey T 8 S R 7 E H-3
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

[Signature]
REGISTER OF DEEDS
MONROE COUNTY, MICH

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____
1993 MONROE COUNTY REMONUMENTATION PROGRAM
Peer Group approved corner on 11/16/1993 per Act 345 of 1990.

I, G.B. WARNKE, JR., in a field survey on 12/21/1994, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3								●					
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

H-3, T8S, R7E, 1/4 Corner Between Sections 3 & 10
(On Samaria Road [M-151] - West of Ann Arbor Railroad)
1820, G.L.O. Surveyor, Joseph Wampler, set quarter post at average distance. Witnesses: W. Oak 40 (inch) East 29 links & W. Oak 24 (inch) N.24°W. 72 links. / Old book notes a stone. / A.J. Marino survey, dated May 10, 1946, notes a plug. / Witness card by L.J. Czibak, Survey Chief, dated March of 1964, notes found railroad spike. / Witness card by W.D. Fletcher, Survey Chief, dated 10-11-65, notes boat spike in monument box. / Monument box, iron in monument box, or iron pin in monument box has been used in the 70's to present. / G.B. Warnke set hex head bolt over pin in monument box without cover.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-3 - On 9/17/1993, Found hex bolt at surface of monument box without lid and witnessed. On 10/27/1993, checked old witness from stone northwest to steps on house. Spoke with owner of residence and found that steps were replaced about 20 years ago and are essentially the same type of steps - witnesses: old 48.5 feet & new 52.86 feet to boat spike. 12/21/1994, set plastic remonumentation cap on bolt.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-3 - Found hex bolt at surface with set plastic remonumentation cap in monument box without lid and is accepted as the best available evidence of the position of the original corner and witnesses:
North 3° East 24.18 feet to nail in south face of telephone pole
North 16° East 63.25 feet to southwest corner of house No. 1362
South 41° East 36.33 feet to nail in northwest face of electric pole
South 20° West 60.18 feet to northeast corner of brick porch of house No. 1405

Signed by [Signature] Date 12/21/1994
Surveyor's Michigan License No. 19474

