

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

94 DEC -9 PM 1:05

RATIFIED BY PEER GROUP
PA 345 OF 1990
MONROE COUNTY, MICHIGAN

date: 11-16-93
County Rep.: [Signature]

For corners in

<u>MONROE</u> <small>(County)</small>	Located In: <u>BEDFORD</u> TWP.	Corner Code <u>#</u> <u>K-2</u>
1. Public Land Survey	T <u>8</u> S R <u>7</u> E	<u>K-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

[Signature]
REGISTER OF DEEDS
MONROE COUNTY, MICH

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____
1993 MONROE COUNTY REMONUMENTATION PROGRAM
Peer Group approved corner on 11/16/1993 per Act 345 of 1990.

1. G.B. WARNKE, JR. in a field survey on 11/11/1994, 19_____
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-2, T8S, R7E, 1/4 Corner Common to Sections 1 & 2
(On Crab) Road between Rauch & Samaria Roads)
1820, G.L.O. Surveyor Joseph Wampler set 1/4 post between Sections 1 & 2. Witnesses: Aspen 10 inch S.16°E. 40 links & Cherry 7 inch S.67°E. 31 links. / Surveys by G.B. Warnke used 1/2 inch iron pipe. / September 1991, G.B. Warnke excavated pieces of 1/2 inch iron pipe and replaced with 1 inch by 36 inch iron pipe. / No other valuable information found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-2 On 10/28/1993, found 1 inch (inside diameter) thick walled iron pipe. 11/11/1994, set brass remonumentation cap on found 1 inch iron pipe inside set monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-2 - Found 1 inch (inside diameter) thick walled iron pipe with set brass remonumentation cap inside set monument box and is accepted as the best available evidence of the position of the original corner and
Witnesses:
North 70° East 88.22' southwest corner of foundation of res'd No. 10990
North 87° East 29.43' found nail/shiner in north face of Walnut
North 75° East 112.80' southeast corner of foundation of res'd No. 10990
South 75° West 32.59' nail/shiner in north face of electric pole

Signed by [Signature]
Surveyor's Michigan License No. 19474

Date 11/11/1994

