

RATIFIED BY PEER GROUP
PA 345 OF 1990
MONROE COUNTY, MICHIGAN

SURVEY &
REMONUMENTATION

APR 28 1995

COMMISSION

date: 8/23/1994
County Rep: [Signature]

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MONROE (County)	Located In: BEDFORD TWP.	Corner Code #
1. Public Land Survey	T 8 S R 7 E	K-6
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1994 MONROE COUNTY REMONUMENTATION PROGRAM

Peer Group approved corner on 8/23/1994 per Act 345 of 1990.

I, G.B. WARNKE, JR., in a field survey on 11/28/1994, 19____ do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-6, T8S, R7E, 1/4 Corner Common to Sections 13 & 14 (Crabb and Vienna Roads - hard surface) 1820, G.L.O. Surveyor set quarter section post and witnessed: B. Oak 23 (inch) N.67°E. 13 links & B. Oak 20 (inch) S.63°W. 101 links. 1956, witness card notes found stone. 1970 to present, found railroad spike used. 1973, Frank R. Moskos recorded L.C.R.C., Liber 1, Page 377, to found railroad spike.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-6 - 7/1994, Found railroad spike and witnessed as shown below. 11/28/1994, set 1 inch x 36 inch iron pipe with brass remonumentation cap inside monument box to replace found railroad spike.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-6 - Set 1 inch x 36 inch iron pipe with brass remonumentation cap inside monument box to replace found railroad spike and is accepted as the best available evidence of the position of the original corner and witnesses:
South 45° East 42.65 feet to telephone/power pole
South 50° West 39.27 feet to telephone/power pole
North 65° West 37.57 feet to set nail in northeast face 14 inch Ash
North 50° East 38.70 feet to street sign at Crabb & Vienna Roads

Signed by [Signature] Date 11/28/1994
Surveyor's Michigan License No. 19474

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2			
3												
4	7		8		9		10		11			
5												
6	18		17		16		15		14		1	
7												
8	19		20		21		22		23		2	
9												
10	30		29		28		27		26		2	
11												
12	31		32		33		34		35		3	
13												

RECEIVED FOR RECORD
94 DEC 16 PM 3:43
REGISTER OF DEEDS
MONROE COUNTY, MICH.
[Signature]

