

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

94 DEC 29 AM 11:11

RATIFIED BY PEER GROUP
PA 345 OF 1990
MONROE COUNTY, MICHIGAN

date: 11/8/1993

County filed in Monroe
For corners in MONROE
(County)

Located In: BEDFORD TWP.
Corner Code # L-3

1. Public Land Survey	T <u>8</u> S R <u>7</u> E	<u>L-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Mari Allen
REGISTER OF DEEDS
MONROE COUNTY, MICH

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims
MONROE COUNTY REMONUMENTATION PROGRAM Peer Group
approved corner on 11/08/1993 per Act 345 of 1990.

I, G.B. WARNKE, JR., in a field survey on 12/19, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-3, T8S, R7E, 1/4 Corner Between Sections 1 & 12
In 1820, G.L.O. Surveyor Joseph Wampler set 1/4 post between Sections 1 & 12. Witnesses: W. Oak 20 inch N65°E. 61 links & W. Oak 23 inch S.20°E. 46 links. / Not much old information found valuable. / Found 1 inch square head bolt in monument box.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-3 - On 10/28/1993, found 1 inch square head bolt in monument box and witnessed below. 12/19/1994, set plastic remonumentation cap on found bolt in monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-3 - Found 1 Inch Square Head Bolt in Monument Box and is accepted as the best available evidence of the position of the original corner and witnesses:
North 60° East 46.48' center of chain link fence post of cemetery fence (46.35' to face)
South 05° West 29.80' found nail in north face of electric pole
North 65° West 43.46' cut "x" in west end of 12 inch concrete culvert thick wall
South 75° West 21.98' "+" in station 506+00
North 20° West 38.58' southeast corner of headstone of Michale Blouch & wife

12/19/1994, set plastic remonumentation cap on found bolt in monument box

Signed by [Signature] Date 12/19/1994

Surveyor's Michigan License No. 19474

