

SURVEY & REMONUMENTATION

FEB 13 1998

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A., 1970

For corners in **SECTION**

Monroe (58)
(County)

Located In: BEDFORD TWP. Corner Code # L-8

- | | | |
|------------------------------------|-------------------------|-------|
| 1. Public Land Survey | T <u>8S</u> R <u>7E</u> | L-8 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

RECEIVED FOR RECORD
 97 DEC 30 PM 3:45
 REGISTER OF DEEDS
 MONROE COUNTY, MICH.
George B. Warnke

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

1997 Remonumentation Program Corner

I, George B. Warnke, Jr., in a field survey on November - December, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and / or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- GLO did not set center of section.
 - 1969 A.J. Marino survey - notes center - no material
 - 1971 Case & Fleck survey, Liber 611, Page 711 - found I.P. center of Sec.
 - 1972 Case & Fleck survey, Liber 627, Page 621 - F.I.P.
 - 1973 Case & Fleck survey, Liber 654, Page 280 - IP. Found center of Sec.
 - 1974 Case & Fleck survey, Liber 679, Page 773 - Iron found
 - M.R. Fleck LCRC, Liber 1, Pages 448-449 - found 3/4" Iron Pipe
 - 1976 G.B. Warnke survey - iron pipe
 - 1992 G.B. Warnke notes - 3/4" I.P.

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- 11/1997, G.B. Warnke set 1" x 36" iron pipe in monument box to replace found 1" dome head bolt at surface over a found 3/4" x 24" pinched pipe 7" deep - no other evidence found.

RATIFIED BY PEER GROUP, PA 345 OF 1990, MONROE COUNTY, MICHIGAN, DATE 11/18/1997, COUNTY REP. *[Signature]*

12/15/97, G.B. Warnke crew set brass remonumentation cap on previously set 1" x 36" pipe in monument box.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Set 1" x 36" pipe with brass remonumentation cap in monument box to replace found 1" dome head bolt at surface over a found 3/4" x 24" pinched pipe. This position was not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner. Witnesses:
- North 75 West 153.50' to found PK nail in easterly face of telephone pole
 - South 80 West 143.10' to found nail & shiner in northerly face of utility pole
 - North 40 West 41.11 feet to found nail & shiner in easterly face of railroad tie in grape arbor
 - South 70 west 94.25' to fd PK nail in westerly face of utility pole

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		13		17		15		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

Signed by *[Signature]*
 Surveyor's Michigan License No. 19474

Date December 16, 1997

