

**SURVEY &  
REMONUMENTATION**

DEC 07 1994

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

RECEIVED FOR RECORD

94 OCT 12 PM 2:18

RATIFIED BY PEER GROUP  
PA 345 OF 1990  
MONROE COUNTY, MICHIGAN

date: 11/16/1993  
County Rep.: [Signature]  
For corners in

*[Signature]*  
REGISTER OF DEEDS  
MONROE COUNTY, MICH

MONROE (County)	Located In:	Corner Code #/1
	BEDFORD TWP.	
1. Public Land Survey	T <u>8 S</u> R <u>7 E</u>	<u>M-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_  
**1993 MONROE COUNTY REMONUMENTATION PROGRAM**  
Peer Group approved corner on 11/16/1993 per Act 345 of 1990.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, G.B. WARNKE, JR., in a field survey on 8/30/1994, 19\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

**M-2, T8S, R7E, West 1/4 Corner of Section 1**  
(On Minx Road) (Also A-2, T8S, R8E)  
1820, G.L.O. Surveyor Joseph Wampler set 1/4 post on east range line of Section 1, T8S, R7E. Witnesses: B. Oak 17 inch S.50°E. 38 links & B. Oak 19 inch S.71°W. 31 links. Examined Bedford & Erie Township files & found no old evidence of corner used. L.A. Howard December of 1903 did survey in northeast 1/4, Section 1, T8S, R7E, but didn't dig corners. Accepted available surveys from 1979 to date.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

M-2 - 1993, gravel road is approximately 18 inches below natural grade passing over a sandy knoll. Evidence of original post was probably obliterated. Found Case & Fleck 1/2 inch x 48 inch iron pipe, which fit occupation east and west. Dug 24 inch x 24 inch x 20 inch hole; found evidence that it had been dug before further west & north. Set 1 Inch x 36 Inch Iron Pipe over reset 1/2 inch iron pipe and witnessed as shown below. 11/16/1993, dug 4 foot x 3 foot (N & S) x 18 inch deep hole to east of iron pipe; No evidence found. 8/30/1994, set brass remonumentation cap on 1 inch x 36 inch iron pipe.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

M-2 - Set Brass Remonumentation Cap on 1 Inch x 36 Inch Iron Pipe over reset 1/2 inch iron pipe & is accepted as the best available evidence of the position of the original corner & Witnesses:  
East 33.00' 1/2 inch capped iron pipe (No. 6193)  
South 85° East 23.00' nail & washer in south face of utility pole  
South 40° East 70.51' roofing nail/shiner in west face of 12 inch Spruce  
South 70° East 94.55' southeast corner of residence No. 10952

igned by [Signature]  
urveyor's Michigan License No. 19474

Date 8/30/1994

