

FEB 13 1998

SECTION

RECEIVED FOR RECORD

97 NOV 12 PM 1:56

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A., 1970

Handwritten signature: Terri Allen, REGISTER OF DEEDS, MONROE COUNTY, MICH

For corners in

Monroe (County)

Located In:

Corner Code #

Form with 5 categories: 1. Public Land Survey, 2. Property Controlling in Section, 3. Miscellaneous Property in Sec., 4. Lot No., 5. Private Claims. Includes Bedford Twp. and M-6 corner code.

Register of Deeds Stamp & File Number

I, George B. Warnke, Jr., in a field survey on 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and / or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1997 Remonumentation Program Corner
1/4 Corner to Section 13 at Minx and Half Mile Roads in gravel surface
Corner Common to A-6, T8S, R8E, Erie Township

- A. Description of original monument and accessories and/or subsequent restoration:
1820, GLO Surveyor, Joseph Fletcher notes set qtr. Section post - witnesses: W Oak 16 N 10 E 78 lks / DO 16 S 86 W 102 lks
1955, AJ Marino field notes show P. R.R. Spike - witnesses: NW 26.7' Tele pole / SW 19.65' St. sign
1956, Witness card shows found spike in pavement
1973, Frank Moskos LCRC (Liber 1, Page 379) shows found nail - witnesses: 31.80' to SW to street sign / 35.00' to NE to wooden paddle type stake / 19.68' to SE to wooden paddle type stake
1975, G. B. Warnke survey (#75-118) shows iron pipe - witnesses: East - 51.52' - West face 8" wood post / S 60° W - 31.69' - E' face road sign post / N 45° W - 52.40' - SE cor. of tel. cable box
1980, G. B. Warnke survey (#80-69) shows iron pipe - same witnesses as 1975 Warnke survey (#75-118)
1983, Case & Fleck survey (#21003) shows found I.P. - witnesses: N 45 W - 52.4' SE Cor. Tele. Box / S 65 W - 32.7' Yield RAW Sign / S 60 W - 31.7' Rd. Sign Post
1997, G. B. Warnke remonumentation crew notes found 3/4" pipe

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
1997, G.B. Warnke field crew excavated 15' x 18' with backhoe to about 30" depth - nothing found. Used 3/4" x 18" pipe found best evidence. Reset corner with 1" x 36" iron pipe in gravel road.

RATIFIED BY PEER GROUP, PA 345 OF 1990, MONROE COUNTY, MICHIGAN, DATE 8/26/1997, COUNTY REP. [Signature]

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set 1" x 36" pipe with brass remonumentation cap to replace found 3/4" x 18" pipe and is accepted as the best available evidence of the original corner. Witnesses:
S 76° W - 110.78' - nail in west face of electric pole
S 47° W - 44.25' - northwest face of electric pole
N 13° W - 132.15' - nail in easterly face of electric pole
N 38° W - 52.26' - southeast corner of GTE pedestal
S 88° E - 51.75' - west face of private drive sign

Signed by [Signature]
Surveyor's Michigan License No. 19474



Date 10/8/1997