

**SURVEY &
REMONUMENTATION**

DEC 07 1994

RECEIVED FOR RECORD

94 OCT 12 PM 2:21

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RATIFIED BY PEER GROUP

1990

MONROE COUNTY, MICHIGAN

date: 11-16-93

County Rep.: [Signature]

For corners in

MONROE
(County)

Located In:

Corner Code ##

BEDFORD TWP.

1. Public Land Survey	T <u>8</u> S R <u>7</u> E.	<u>M-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

[Signature]
REGISTER OF DEEDS
MONROE COUNTY, MICH

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

1993 MONROE COUNTY REMONUMENTATION PROGRAM

Peer Group approved corner on 11/16/1993 per Act 345 of 1990.

I, G.B. Warnke, Jr., in a field survey on 8/29/1994, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-11, T8S, R7E, Section Corner Common to Sections 25 & 36

(On Sterns Road - North of Chesapeake & Ohio Railroad - hard surface)

1820, G.L.O. Surveyor Joseph Wampler set post at corner of Sections 25 & 36 and witnesses: Hickory 11 inch N.46°E. 13 links & Ash 10 inch S.25°W. 11 links. / 1886, Willis Baldwin noted stone and witness N.79°E. 146.52 feet to 24 inch Cottonwood. / A.J. Marino, dated May 1970, notes old iron 3 feet deep with 2 witnesses. / 1981 & 1982, MDOT Survey on M-125 (Dixie Hwy.), Glen Hobgood excavated & witnessed 1/2 inch iron rod & placed monument box per LCRC, Liber 2, Page 435. / 1992, G.B. Warnke found 1/2 inch iron rod in monument box.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-11 - Found 1/2 inch iron rod inside monument box and witnessed. On 8/29/1994, 1/2 inch rod could not be removed. Placed remonumentation cap on rod and witnessed as shown below.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-11 - Found 1/2 Inch Iron Rod Inside Monument Box and Set Remonumentation Cap on Rod and is accepted as the best available evidence of the position of the original corner and witnesses:
 South 20° West 30.12 feet nail/shiner (MDOT) in northwest face of guy pole
 North 20° West 45.30 feet nail/shiner (MDOT) in east face of electric pole
 North 84°19'31" West 2660.75 feet PK nail/washer at South 1/4 corner, Section 25, T8S, R7E
 South 89°53'30" East 2659.85 feet broken concrete monument in monument box at South 1/4 corner, Section 30, T8S, R8E

Signed by [Signature]
 Surveyor's Michigan License No. 19474

Date Aug 29, 1994