

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD
 94 NOV 23 AM 10:50
 REGISTER OF DEEDS
 MICHIGAN DEPARTMENT OF PUBLIC SAFETY

RATIFIED BY PEER GROUP
 PA 345 OF 1990
 MONROE COUNTY, MICHIGAN
 Date: 7/12/1994
 County Rep.: [Signature]
 For corners in: [Signature]

<u>MONROE</u> (County)	Located In: <u>ERIE TWP.</u>	Corner Code: <u>A-4</u>
1. Public Land Survey	T <u>8 S</u> R <u>8 E</u>	<u>A-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims
1994 MONROE COUNTY REMONUMENTATION PROGRAM
 Peer Group approved corner on 7/12/1994 per Act 345 of 1990.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

G.B. WARNKE, JR. in a field survey on 9/2/1994, 19____
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules theretofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

6. Description of original monument and accessories and/or subsequent restoration:

A-4, T8S, R8E, West 1/4 Section Corner to Section 7
 (On Minx Road - 1/2 Mile South of Samaria Road) (Common to M-4, T8S, R7E - Approved in 1993)
 1820, G.L.O. Surveyor Joseph Wampler set 1/4 post for Section 12 on the east range line and witnesses:
 B. Oak 26 inch S.40°E. 200 links. 1942, A.J. Marino notes stone found in survey in southeast 1/4 of Section 12. June 1943, Consumers Power survey by Turner witnessed stone. Case & Fleck witness card, dated October 1973, & 1973 survey (Liber 657, Page 46) notes stone. 1975, 1980 & 1990, G.B. Warnke witnessed stone. 11/22/1993 - George Warnke crew found 16 inch long pinch pipe 1 1/2 inches below gravel road and 6 inches above high point of stone found 21 1/2 inches deep.

7. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-4 - 3/28/1994, found 1/2 inch pinched pipe 1 1/2 inches below gravel road and witnessed as shown below. 9/2/1994, dug up corner and found 1/2 inch pinch pipe over high point of 12 inch long red granite stone with base at approximately 30 inches deep. Dug to approximately 40 inches deep in white/gray sand. No evidence of post or other material. Set 1 inch x 36 inch iron pipe and brass remonumentation cap with stone on south side and the 1/2 inch iron pipe on north side below 1 inch iron pipe to assist in stabilizing point.

8. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-4 - Set 1 inch x 36 inch iron pipe and brass remonumentation cap with stone on south side and the 1/2 inch iron pipe on north side below 1 inch iron pipe to assist in stabilizing point to replace 1/2 inch iron pipe over stone & is accepted as the best available evidence of the position of the original corner & Witnesses:
 East 33.00 feet to top of Consumer Powers monument (2 inch diameter pipe with twist cap on top, in concrete, 2.4 feet out of ground & leaning to the north)
 East 28.67 feet to nail/washer in west face of electric pole
 North 20° East 104.45 feet nail/washer in southwest face of southerly pole of most southerly "H" frame
 West +/- 2 feet to west edge of gravel, fairly large road ditch north & south along west edge of pavement
 West 32.72 feet to top of Consumer Powers monument (1.0 foot out of ground)
 South 45° West 28.36 feet to top of gate not on east end of 6 inch plastic field tile

Signed by [Signature] Date 9/2/1994
 Surveyor's Michigan License No. 19474