

**SURVEY &
REMONUMENTATION**

DEC 07 1994

COMMISSION

RATIFIED BY PEER GROUP
PA 345 OF 1990
MONROE COUNTY, MICHIGAN

RECEIVED FOR RECORD

date: 7/12/1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

94 OCT 12 PM 2:45

County Rep.: [Signature]
For corners in

Mari Allen
REGISTER OF DEEDS
MONROE COUNTY, MICH

<u>MONROE</u> (County)	Located In:	Corner Code #/
	ERIE TWP.	
1. Public Land Survey	T <u>8</u> S R <u>8</u> E	<u>A-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

1994 MONROE COUNTY REMONUMENTATION PROGRAM

Peer Group approved corner on 7/12/1994 per Act 345 of 1990.

I, G.B. WARNKE, JR., in a field survey on AUGUST 29, 1994, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-11, T8S, R8E, Corner of Sections 30 & 31, T8S, R8E, and 25 & 36, T8S, R7E
(On Sterns Rd. - North of Chesapeake & Ohio Railroad) (Also M-11, T8S, R7E - Approved in 1993)
1820, G.L.O. Surveyor Joseph Wampler set post at corner of Sections 25 & 36. Witnesses: Hickory 11 inch N.46°E. 13 links & Ash 10 inch S25°W 11 links. / 1886, Willis Baldwin noted stone. Witness: N.79°E. 146.52' to 24 inch Cottonwood. / A.J. Marino, dated May of 1970, notes old iron 3 feet deep with 2 witnesses. / 1981 & 1982, MDOT Survey on M-125 (Dixie Hwy.), Glen Hobgood (#21571) for M.S.H.D. excavated & witnessed 1/2 inch iron rod & placed monument box per LCRC, Liber 2, Page 435. / 1992, G.B. Warnke found 1/2 inch iron rod in monument box.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-11 - On 7/25/1992, found 1/2 inch iron rod in monument box and witnessed, On 8/29/94, 1/2 inch iron rod could not be removed, placed remonumentation cap on rod and witnesses as shown below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-11 - Found 1/2 inch Iron Rod with Set Remonumentation Cap in Monument Box & is accepted as a careful and faithful perpetuation of the position of the original corner & Witnesses:
South 20° West 30.12' nail/shiner (MDOT) in northwest face of guy pole
North 20° West 45.30' nail/shiner (MDOT) in east face of electric pole
North 84°19'31" West 2660.75' PK nail/washer at South 1/4 Corner of Section 25, T8S, R7E
South 89°53'30" East 2659.85' broken concrete monument in monument box at South 1/4 Corner of Section 30, T8S, R8E

Signed by [Signature]
Surveyor's Michigan License No. 19474

Date 9/29/1994



FORM APPROVED BY MICHIGAN BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983