

SURVEY & REMONUMENTATION

FEB 13 1998

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A., 1970**

For corners in

MONROE (58)

(County)

Located In:

Corner Code #

ERIE TWP.

T8S R8E

E-6

1. Public Land Survey

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

1997 Remonumentation Program Corner

I, George B. Warnke, Jr., in a field survey on September - December, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and / or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1820 GLO, Joseph Wampler, between Secs. No. 16 & 17 - Set the 1/2 mile post from which a B. Oak 5 ins. dia. bears S22E 30 lks. dis & a B. Oak 17 ins. dia. bears N27E 76 lks. dis.
- 1953 A.J. Marino notes - P. Cross
- 1950's? Section Corner References - copy found in G.B. Warnke files - Cross in Pave. - witnesses: Nails in Tel Poles @ NE 91.8 & SWw 66.35 & SE 87.40
- 1955 A.J. Marino notes - F. Cross
- 1966 A.J. Marino notes - P.K. Nail
- 1968 A.J. Marino notes - Nail
- 1971 A.J. Marino notes - F. P.K. Nail
- 1975 A.J. Marino notes - F.I.P.
- 1979 G.B. Warnke, LCRC, Liber 2, Page 456 - Bolt in Monument Box - witnesses: S45°E - nail & shiner N.E. face power pole; 96.20' S60°W - nail & shiner S.E. face tel. pole; 82.50' N45°E - nail & shiner S.W. face power pole; 87.20'
- 1991 G.B. Warnke survey #91-0211 - Found iron bolt in monument box - witnesses: S45°E 96.17 feet to nail & shiner in NW. face util. pole S60°W 82.48 feet to nail & shiner in SE. face util. pole N45°E 87.25 feet to nail & shiner in SW. face util. pole N50°W 116.45 feet to nail & shiner in E. face util. pole

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

9/16/1997, G.B. Warnke found 1" hex bolt in monument box @ US 24 & Vienna Road. Checked point with G.B. Warnke's 1979 LCRC witnesses, which were within reason.

RATIFIED BY PEER GROUP, PA 345 OF 1990, MONROE COUNTY, MICHIGAN, DATE 12/9/1997, COUNTY REP.

12/1997 Wired on plastic remonumentation cap to found 1" hex bolt in monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Wired on plastic remonumentation cap to found 1" hex bolt in monument box and is accepted as the best available evidence of the position of the original corner. Witnesses:
 96.12 feet South 45° East - nail & shiner in northeasterly face of P. pole
 82.50 feet South 60° West - nail & shiner in southeasterly T. pole
 87.27 feet North 45° East - nail & shiner in southwesterly face of P. pole
 116.51 feet North 45° West - found nail & shiner in easterly face of telephone pole
 6 feet East of centerline of pavement

Signed by _____
 Surveyor's Michigan License No. 19474



Date December 16, 1997

RECEIVED FOR RECORD
 97 DEC 30 PM 3:24
 Register of Deeds
 MONROE COUNTY, MICH

Register of Deeds Stamp & File Number

