

MAY 20 1997

COMMISSION

RECEIVED FOR RECORD

96 DEC 13 PM 3:22

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A., 1970

Scott A. Warnke
REGISTERED PROFESSIONAL SURVEYOR
MICHIGAN LICENSE NO. 41913

For corners in

Monroe
(County)

Located In:

Corner Code #

1. Public Land Survey

Erie Twp.

T 8S R 8E

G-4

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

1	A	B	C	D	E	F	G	H	I	J	K	L
2		6		5		4		3		2		1
3												
4		7		8		9	●	10		11		12
5												
6		18		17		16		15		14		13
7												
8		19		20		21		22		23		24
9												
10		30		29		28		27		26		25
11												
12		31		32		33		34		35		36
13												

I, Scott A. Warnke, in a field survey on October, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and / or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Monroe County Road Commission Corner

A. Description of original monument and accessories and/or subsequent restoration:

Quarter corner common to Sections 9 & 10, T8S, R8E / Bay Creek & Grodi Roads, currently gravel, will be paved.
1820 GLO Surveyor Wampler set wood post; Hickory 10", S8W, 8 links; Do. 9", N26W, 14 links
1942, Consumers Power Co., Found 5"x10" stone, set iron over stone & glass around stone; Power pole, NW, 33.6';
Power pole, SE, 65.80'; 18" Apple, SE, 106.0'
1943, Consumers Power Co., same as above
Date unknown, Case sketch; no desc. of monument, same witnesses as above
1976, G.B. Warnke Survey #76-93, found iron leaning over stone; S40E, 39.82', Nail in SW face of twin crab apple;
N70E, 68.28', Nail in S face of elec. pole; N45W, 33.85', Nail in S face of utility pole
1976, G.B. Warnke Survey #76-155; same monument and witnesses as Survey #76-93 above.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found iron bent over stone. Excavated 3'x3'x3' hole. Found glass around stone. No other evidence found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1" x 36" iron pipe with brass remonumentation cap inside monument box to replace stone and is accepted as the best evidence of the position of the original corner.

Witnesses:

N28E, 105.68', Nail/shiner W face of power pole
N64E, 92.16', Nail/shiner SE face of power pole
N82E, 68.39', Nail/alum. coin S face of utility pole
S44E, 51.53', Nail/shiner S face of utility pole
N60W, 33.04', Nail/alum. coin SW face of utility pole

RATIFIED BY PEER GROUP
PA 345 OF 1990
MONROE COUNTY, MICHIGAN

date: 11/21/96
County Rep.: [Signature]



Signed by Scott A. Warnke

Date 11-26-96

Surveyor's Michigan License No. 41913