

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A., 1970

For corners in
MONROE (58)
 (County)

1. Public Land Survey
2. Property Controlling in Section
3. Miscellaneous Property in Sec.
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Located In: ERIE TWP.
T 8 S R 8 E
 Corner Code # H-5

S _____ T _____ R _____
 S _____ T _____ R _____
 S _____ T _____ R _____
 S _____ T _____ R _____

REGISTER OF DEEDS
 MONROE COUNTY, MICH.
David Allen

RECEIVED FOR RECORD
 99 DEC 28 AM 8:57

1999 Remonumentation Program Corner

I, George B. Warnke, Jr., in a field survey on October, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and / or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5								★					
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1827 - GLO - Robert Clark - 40.01 / Set the 1/4 sec. post at average distance in wet prairie
- 1954 - State Highway Project (I-75) - N. on N.&S. 1/4 Line - 33' - 2" Pipe
 - S68°W 53.27' 14" Ash
 - S56°W 35.44' 12" Ash
 - S23°W 21.83' 14" Ash
 - N69°E 110.45' 18" Maple
 - Cross in CL pavt.
- 1/1968 - MSHD - Ackerman [bolt] in Pavt on Erie Rd. Brid [bridge]-
 - Chis "X" on bridge catwalk S17°W 13.2
 - Chis "X" on bridge catwalk N39°W 22.8
 - Chis "X" on bridge catwalk N13°E 13.2
 - Chis "X" on bridge catwalk N42°E 25.7
- 1/1991 - G.B. Warnke - Survey #91-0002 - field evidence reveals corner was lost during construction on I-75.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner is located in bridge deck over I-75 on Erie Road - not monumented by M.D.O.T. - in hard (concrete?) pavement.
 1999 - Using G.P.S., Monroe County Road Commission & MSHD notes, determined location & we will set remonumentation cap on bridge deck over I-75. The concrete pavement on deck has been repaired. No bolt was found.
 10/22/1999 - drilled hole & chiseled area & set 1/2" x 6" carriage bolt with yellow remonumentation cap epoxied into bridge deck.

RATIFIED BY PEER GROUP, PA 345 OF 1990, MONROE COUNTY, MICHIGAN, DATE 7/13/1999, COUNTY REP. *[Signature]*
 Corner is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1/2" x 6" carriage bolt with yellow remonumentation cap epoxied into bridge deck & Witnesses:
 North 13.06 feet to face of concrete curb
 South 13.01 feet to face of concrete curb
 North 88°46' West 140.11 feet to southeast corner of west concrete post for north railing
 South 80° West 158.05 feet to northeast corner of west concrete post of south railing
 South 85°47' East 93.52 feet to northwest corner of east concrete post of south railing

Signed by *[Signature]*
 Surveyor's Michigan License No. 19474



Date October 26, 1999