

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A., 1970

For corners in MONROE (58) (County)

Located In: Corner Code #

- 1. Public Land Survey
2. Property Controlling in Section
3. Miscellaneous Property in Sec.
4. Lot No. Recorded Plat
5. Private Claims

ERIE TWP. T 8 S R 8 E

1-5

RECEIVED FOR RECORD
99 DEC 29 AM 8:58
REGISTER OF DEEDS
MONROE COUNTY, MICH

1999 Remonumentation Program Corner

I, George B. Warnke, Jr., in a field survey on May - September, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and / or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1827 - GLO - Robert Clark - set post corner of Secs. 10, 11, 14 & 15 in Mound
10/1942 - surveyor? [can't read name] - partial copy of Drawing for Consumers Power - Found Iron in Pavement
1954 - State Highway Project 58-57 (I-75) - motor valve in CL of pavt. - S52°W 60.88' center M.H. cover & N24°W 51.07' P.P.
2/1943 - found in files / Marino's ? - found iron in CL of pavement
12/1958 - A. J. Marino - notes - found old cross
1963 - A. J. Marino - notes - F. valve
12/1966 - A. J. Marino - notes - F. valve
1/1968 - MSHD - Sec. Cor. Comm. to 10-11-14-15 - Motor Valve in CL Pav't - Ctr. of M.H. S65°W 60.92' & P. Pole N65°W 51.12'
7/1973 - M. R. Fleck / Case & Fleck - Job #17730 / Liber 652, Page 715 - no corner material or witnesses
9/1980 - M. R. Fleck / Case & Fleck - Job #20829 / Liber 827, Page 309 - no corner material or witnesses
8/1982 - M. R. Fleck / Case & Fleck - Job #5495-A / Liber 864, Page 250 - no corner material or witnesses

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 1-13. A star symbol is located at the intersection of row 5 and column I.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner is located in Erie Road / in asphalt over concrete pavement / 1/4 mile east of Grodi & 1/2 mile east of I-75.
5/1999 - Found small PK / witnessed set nail & shiner 4.00 east & north. Found 2 witnesses from 1968 MSHD to an auto engine valve which fell 0.35 east & 0.4 south of PK nail. Dug through 4" asphalt - 6" to 8" of concrete pavement was deteriorated or broken up. Auto valve not found. Dug hole SW to NE 28" x 20" x 24" deep. Used post hole digger 8" diameter x 14" - found some wood - 1 piece appears charred. Set 1/4" pin in bottom inside 3-1/2" clay tile using 2 witnesses to valve. Set 1" x 36" pipe over pin in monument box. 9/21/99 - set brass cap on 1" x 36" iron pipe.

Handwritten signature

RATIFIED BY PEER GROUP, PA 345 OF 1990, MONROE COUNTY, MICHIGAN, DATE 7/13/1999, COUNTY REP.

Corner is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set 1" x 36" pipe with set brass remonumentation cap over pin in set monument box & Witnesses:
South 65° West 60.92 feet to center of manhole
North 65° West 51.12 feet to reset nail & shiner in southerly face of old electric pole
South 50° West 122.1 feet to northwest corner of 5" square post
West 156 feet to centerline of concrete drive south Consumer's Power
North 10° West 109.88 feet to double head nail in east face of Cottonwood in center of pavement



Signed by [Signature]
Surveyor's Michigan License No. 19474

Date October 26, 1999