

RATIFIED BY PEER GROUP
PA 345 OF 1990
MONROE COUNTY, MICHIGAN

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

date: 10/24/1995
County Rep.: [Signature]
For corners in
Monroe (58)

RECEIVED FOR RECORD
95 DEC 29 AM 9:07
REGISTER OF DEEDS
MONROE COUNTY MICH

(County)	Located In:	Corner Code #:
1. Public Land Survey WHITEFORD TWP.	T <u>9S</u> R <u>6E</u>	<u>M-1</u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u>SURVEY & REMONUMENTATION</u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims COMMISSION
1995 REMONUMENTATION PROGRAM
Peer Group approved 10/24/1995 per Act 345 of 1990

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, G.B. WARNKE, JR., in a field survey on 1994 & 1995, 19 , do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Northeast corner of Section 1 and Township, T9S, R6E / At Smith Road & Pelton Drive in pavement.
(Common Corners: A-1, T9S, R7E & A-13, T8S, R7E & M-13, T8S, R6E & M-1, T9S, R6E)
1820, G.L.O. Surveyor, Joseph Wampler, set post at corner of Township 8 & 9 South, Range 6 & 7 South - witnesses:
B. Oak 18 N.45W. 4 lks & B. Oak 11 S.31E. 54 lks. / Stone noted by Winney, 1893. 10/1930, J.W. White notes stone.
A.J. Marino notes stone in June 1940 & Aug. 1952 & Nov. 1957. 1970, Farnham, Moores & Wirries notes small bolt.
1973, M.R. Fleck recorded survey, Liber 650, Page 492, & LCRC, Liber 1, Page 353, notes R.R. spike over stone.
1974, G.B. Warnke, Job #74-65, set 5/8" I. pin (to replace R.R. spike) over stone & found same in 1978, Job #78-17. 1989, G.B. Warnke recorded LCRC, Liber 3, Page 82, to found P.K. nail per Fleck LCRC witnesses. 10/1993, found 5/8 inch x 9 1/2 inch small engine shaft over stone being approximately 8 inches deep. 12/1994, set 1" x 36" iron pipe with brass remonumentation cap inside monument box.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

10/1995 - checked point and witnesses per LCRC's for A-13, T8S, R7E, & A-1, T9S, R7E, which is a common corner. Rechecked 1" iron pipe with brass remonumentation cap in monument box

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

^{FOUND}
1" x 36" iron pipe with brass remonumentation cap in monument box and is accepted as the best available evidence of the position of the original corner and witnesses:
S40°W 74.65' northeast corner of foundation of house No. 4301
S45°W 40.13' found nail/shiner in northeast face of telephone pole
N60°W 60.33' found P.K. nail/shiner in southwest face of telephone pole
N15°E 86.09' southwest corner of siding on attached garage at house No. 4298
(previous witness to foundation, now broken)
S10°E 29.75' found nail/shiner in northerly face of 30" Oak
N60°E 83.55' found P.K. nail/shiner in southeast face of utility pole



igned by [Signature] Date 12/4/1995
urveyor's Michigan License No. 19474