

sections 1 and 2; 2,482.05 feet north of approximate corner sections 1, 2, 11 and 12.

Property east owned by W. Wright. Property west owned by L. Strong.

(Latitude $41^{\circ} 43' 21.48''$ Longitude $83^{\circ} 46' 51.38''$)
To Post 52, true bearing N. $87^{\circ} 42' 25''$ E. Distance 5,024.7 feet.

POST 52.

On east side of north-south road between section 1, R. 5 E. and section 6, R. 6 E., T. 9 S., 0.5 mile north of Smith Sidling. Post 44.0 feet south and 22.0 feet east of stone, quarter corner west side of section 6. Adjacent property east and west owned by J. A. Wilson.

(Latitude $41^{\circ} 43' 23.46''$ Longitude $83^{\circ} 45' 45.12''$)
To Post 53, true bearing N. $87^{\circ} 50' 42''$ E. Distance 5,095.2 feet.

POST 53.

On west side of north-south road between sections 5 and 6, T. 9 S., R. 6 E. Opposite old stake found in center of road, started by Edw. Ward to mark line between his farm and that of F. Knapp; 30.2 feet east of 2 foot elm tree on property line, started by Frank Knapp and Edw. Ward to have been accepted for 40 years or more as on state line. South 2,538.0 feet to center of crossroads, approximate corner sections 5, 6, 7 and 8. North 2,567.0 feet to center of crossroads approximate corner sections 5, 6, 31 and 32. State line west divides the property of Edw. Ward on the north and Frank Knapp on the south. Adjacent property east owned by David Anderson.

(Latitude $41^{\circ} 43' 25.35''$ Longitude $83^{\circ} 44' 37.08''$)
To Post 54, true bearing N. $87^{\circ} 17' 21''$ E. Distance 5,400.1 feet.

POST 54.

Two feet west of north-south wire fence on line between sections 4 and 5, T. 9 S., R. 6 E.; 4.5 feet northwest of 20 inch elm. One mile west by 0.5 mile north of Sylvania. Post 2,482.7 feet south of stone, corner sections 4, 5, 32 and 33. Stone 1.8 feet north of center line east-west road on line with north-south fence. Post 2,434.2 feet north of stone, corner sections 4, 5, 8 and 9. Stone 6 inches below surface of road set over another stone and is S. 6° (approximate) W. 47.0 feet from 18 inch hickory and directly south 63 feet from another 18 inch hickory. Post on property of Frank Wenzler. Property east owned by Mrs. J. Scholl.

(Latitude $41^{\circ} 43' 27.57''$ Longitude $83^{\circ} 43' 26.85''$)
To Post 54A, true bearing N. $88^{\circ} 00' 44''$ E. Distance 4,122.9 feet.

POST 54A.

A concrete post of the Lake Shore & Michigan Southern R. R. on west line of railroad right of way in section 4 T. 9 S., R. 6 E. on north line of Sylvania corporation. The post is triangular in shape and projects about 8 feet above ground. Marked "Mich." on north and "Ohio." on south. This post replaces a wooden post set by the same railroad which had been accepted for many years as the state line and as it agreed closely with the line as surveyed in 1915, it has been adopted as a mark on the final line.

(Latitude $41^{\circ} 43' 29.38''$ Longitude $83^{\circ} 42' 32.51''$)
To Post 55, true bearing N. $87^{\circ} 22' 25''$ E. Distance 1,337.7 feet.

POST 55.

On north-south fence line between sections 3 and 4, T. 9 S., R. 6 E.; 0.5 mile north of Sylvania on north boundary of corporation; 435.5 feet south of iron pin in east-west road marking quarter corner between sections 3 and 4. Post 2,210.1 feet north of iron pin, corner sections 3, 4, 9 and 10. Pin 6 inches below surface of east-west road in Sylvania; 57.0 feet east of catch basin; 49.3 feet north of north-west corner M. Cunniff's house and 41.5 feet south of south brick wall of K. J. Carfield's house. Property west owned by E. L. Fowler. Property east owned by Mary Hattersley.

(Latitude $41^{\circ} 43' 29.89''$ Longitude $83^{\circ} 42' 14.89''$)
To Post 56, true bearing N. $85^{\circ} 27' 54''$ E. Distance 887.9 feet.

POST 56.

On east side of road running north northeast and south southwest through section 3, T. 9 S., R. 6 E.; 2 feet west of north-south wire fence. Post is on north boundary of Sylvania corporation. Property both east and west owned by Mary Hattersley.

(Latitude $41^{\circ} 43' 30.58''$ Longitude $83^{\circ} 42' 03.22''$)
To Post 57, true bearing N. $85^{\circ} 29' 09''$ E. Distance 4,416.4 feet.

POST 57.

On east side of north-south road between sections 2 and 3, T. 9 S., R. 6 E.; 2 feet west of north-south wire fence and 38.6 feet south of anchor post of fence east. Post is 129.87 feet south of stone, quarter corner sections 2 and 3. Stone in center line north-south road, 31 feet north of north fence of road east. Post is 2,421.93 feet north of stone corner sections 2, 3, 10 and 11. Stone in center line road opposite center line lane east from stone 75.6 feet southeast to 24 inch oak tree and 39.2 feet northwest to 8 inch apple tree. Property east of post 57 owned by H. A. Hine. Property west owned by T. H. Walbridge.

(Latitude $41^{\circ} 42' 34.01''$ Longitude $83^{\circ} 41' 05.19''$)
To Post 58, true bearing N. $88^{\circ} 50' 19''$ E. Distance 5,261.4 feet.

POST 58.

On east side of north-south road between sections 1 and 2, T. 9 S., R. 6 E.; 48.6 feet northwest of northwest corner of A. Shabnow's house; 104.5 feet south of stone, quarter corner between sections 1 and 2. Post 2,509.2 feet north of iron pipe, center line north-south road, opposite fence west, marking corner sections 1, 2, 11 and 12. Post on lot of A. Shabnow. Property west owned by Albert Miller.

(Latitude $41^{\circ} 43' 35.06''$ Longitude $83^{\circ} 39' 55.79''$)
To Post 59, true bearing N. $87^{\circ} 39' 59''$ E. Distance 7,103.3 feet.

POST 59.

On west side of north-south road through section 6, T. 9 S., R. 7 E.; 0.3 mile east of range line, opposite stone in center line of road and fences east-west. Stone in road pointed out by residents as having been accepted for many years as being on state line. Fence east divides property of F. Coon on the north from B. F. Edwards on the south. Line west divides property of John Dastner on the north from Whinnifd Nicholas on the south.

(Latitude $41^{\circ} 43' 37.91''$ Longitude $83^{\circ} 38' 22.19''$)
To Post 60, true bearing N. $87^{\circ} 23' 00''$ E. Distance 4,277.7 feet.

POST 60.

On east side of north-south road between sections 5 and 6, T. 9 S., R. 7 E.; 0.5 mile north of Trilby; in line with south side of J. A. Brock's house; 62.7 feet west of west side of same house; 5.0 feet south of 10 inch elm; 55.9 feet north of stone, quarter corner sections 5 and 6, on west side of stone road, on edge of ditch opposite large oak tree. Post 2,399.8 feet south of center of crossroads approximate corner sections 5, 6, 31 and 32. Post on property of J. A. Brock. Property west owned by Saml Cowell.

(Latitude $41^{\circ} 43' 39.84''$ Longitude $83^{\circ} 37' 25.84''$)
To Post 61, true bearing N. $87^{\circ} 09' 07''$ E. Distance 5,218.7 feet.

POST 61.

On east side of north-south road between sections 4 and 5, T. 9 S., R. 7 E.; 2 feet west of north-south board fence; 179.9 feet north of fence west pointed out by Will Frazier as being on the one-half section line; 2,303.1 feet south of center of crossroads, opposite center line of bridge east, approximate corner sections 4, 5, 32 and 33. Property east owned by J. N. Smith. Property west owned by C. Graber.

(Latitude $41^{\circ} 43' 42.40''$ Longitude $83^{\circ} 36' 17.10''$)
To Post 62, true bearing N. $88^{\circ} 46' 50''$ E. Distance 5,389.1 feet.