

POST 62.

On west side of north-south road between sections 3 and 4, T. 9 S., R. 7 E.; 14.5 feet south of south rail of Toledo, Ann Arbor & Jackson R. R.; 15.0 feet east of north-south wire fence and 12.5 feet west of center line of paved roadway. Post 289.78 feet north of east-west fence pointed out as being on one-half section line; 2,345.42 feet south of north corner of sections 3 and 4. Corner marked by wooden stake above stone 2 feet below surface of road. Stake 42.5 feet northwest of telephone pole; 33.7 feet west of 1 foot brace pole; 8.1 feet south east of mail box post; 21.7 feet south of east-west wire fence. Property east owned by Wm. Ellis. Property west owned by C. Stringer.

(Latitude 41° 43' 45.53" Longitude 83° 35' 06.08")
To Post 63, true bearing N. 87° 29' 10" E. Distance 5,152.2 feet.

POST 63.

On east side of north-south road between sections 2 and 3, T. 9 S., R. 7 E.; 1.2 feet east of north-south wire fence; 397.70 feet north of west fence pointed out by S. Curson as on the one-half section line; 2,258.30 feet south of center of crossroads pointed out by S. M. Koch as the corner of sections 2, 3, 34 and 35. Post on property of S. Curson. Property west owned by Wm. Bevans.

(Latitude 41° 43' 45.75" Longitude 83° 33' 58.43")
To Post 64, true bearing N. 88° 29' 59" E. Distance 5,202.5 feet.

POST 64.

At southwest corner of crossing of north-south road between sections 1 and 2, T. 9 S., R. 7 E. and east-west road through center of sections 1 and 2; 3 feet east of north-south wire fence and 5 feet north of east-west wire fence; 400.15 feet north of stone quarter corner between sections 1 and 2, T. 9 S., R. 7 E. in center line of north-south road, opposite fence west. Stone and stake 20.5 feet east of north-south fence. Post 2,217.4 feet south of center of cross roads, approximate corner sections 1, 2, 35 and 36. Property east owned by C. Tye. Property west owned by John Barker.

(Latitude 41° 43' 47.09" Longitude 83° 32' 49.84")
To Post 65, true bearing N. 87° 02' 32" E. Distance 4,484.5 feet.

POST 65.

On east side of Detroit Ave., in section 1 T. 9 S., R. 7 E.; opposite fence east along north side of church yard, pointed out by Moses Lavozy (resident for 45 years) as having been accepted for many years as state line. Post 2.5 feet west of anchor post of said fence east; 51.7 feet northwest of northwest corner of brick church. Line east divides property of L. Lavozy from church yard. Property west owned by M. Lavozy.

(Latitude 41° 43' 49.37" Longitude 83° 31' 50.73")
To Post 66, true bearing N. 88° 05' 49" E. Distance 870.3 feet.

POST 66.

In section 6, T. 9 S., R. 8 E.; on Detroit, Monroe & Toledo Short Line R. R. right of way; 37.67 feet east of east rail of tracks; 1.5 feet west of north-south wire fence; on line with north fence of cemetery, which is on line with fence along north side of church yard (see Post 65), accepted for many years as state line. Post is 2,081.0 feet south of approximate corner of sections 6 and 31, R. 8 E. Line west divides the property of L. Lavozy from cemetery. Property east owned by M. Reed.

(Latitude 41° 43' 49.65" Longitude 83° 31' 39.31")
To Post 66A, true bearing N. 87° 27' 23" E. Distance 1,867.9 feet.

POST 66A.

A concrete post of the Lake Shore & Michigan Southern R. R. on east side of railroad in section 6, T. 9 S., R. 8 E.; 5 miles northeast of Toledo. The post is triangular in shape, about 18 inches on each side and projects 8 feet above ground; marked "Mich." on north side and "Ohio" on south. This post like post 64A, set

by the same railroad north of Sylvania, has been accepted for many years as on the state line and as it agreed closely with the line as surveyed in 1915, it has been adopted as a mark on the final line.

(Latitude 41° 43' 50.47" Longitude 83° 31' 14.70")
To Post 67, true bearing N. 88° 30' 09" E. Distance 3,370.5 feet.

POST 67.

On east side of north-south road between sections 5 and 6, T. 9 S., R. 8 E.; opposite line of cherry trees east. Post 73.8 feet from southwest corner concrete porch, house of C. Mollenhauer; 440.4 feet north of quarter corner sections 5 and 6, fence east 1,885.6 feet north corner sections 5 and 6 fence east pointed out by Nicholas Spores as being on the section line. Property east owned by C. Mollenhauer. Property west owned by Edw. Collins.

(Latitude 41° 43' 51.34" Longitude 83° 30' 30.26")
To Post 68, true bearing N. 87° 52' 47" E. Distance 4,559.0 feet.

POST 68.

On east side of Michigan Ave., in section 5, T. 9 S., R. 8 E.; 2 feet west of anchor post of fence east. Fence said by residents to have been accepted for many years as state line; 58.3 feet southwest of south-west corner L. Morn's house; 42.0 feet southwest of 30 inch oak tree. Line east divides property of L. Morn on the north from R. Petee on the south. Line west divides property of L. Morn on the north from Geo. Symon on the south.

(Latitude 41° 43' 53.00" Longitude 83° 29' 30.17")
To Post 69, true bearing N. 88° 00' 00" E. Distance 4,748.0 feet.

POST 69.

In section 4, T. 9 S., R. 8 E.; 1.25 feet east of north-south wire fence east of timber; 6.3 feet northwest from 30 inch elm. Post replaced a stone 3 inches by 6 inches, 4 inches above ground, said by H. A. McLeary (old resident) to have been set on the state line about 40 years ago. Post on property of H. A. McLeary. Adjacent property west owned by John Brown.

(Latitude 41° 43' 54.63" Longitude 83° 28' 27.59")
To Post 70, true bearing N. 87° 49' 34" E. Distance 3,056.8 feet.

POST 70.

A dressed granite monument, 48 inches by 30 inches by 18 inches, weighing about 2,500 pounds; lettered as follows:
On north side—

MICHIGAN
WOODBRIIDGE N. FERHIS
GOVERNOR
ERECTED BY AUTHORITY OF
THE 48TH LEGISLATURE
ACT 84. PUBLIC ACTS OF 1915
BY MICHIGAN GEOLOGICAL SURVEY
R. C. ALLEN, DIRECTOR
JOINTLY WITH THE STATE OF
OHIO

On south side—

OHIO
FRANK B. WILLIS
GOVERNOR
ERECTED BY AUTHORITY OF
THE 81ST GENERAL ASSEMBLY
ACT OF MAY 27, 1915
BY OHIO TOPOGRAPHIC SURVEY
C. E. SHERMAN, INSPECTOR
JOINTLY WITH THE STATE OF
MICHIGAN