SURVEY & REMONUMENTATION

RATIFIED BY PEER GROUP PA 345 OF 1990 MONROE COUNTY, MICHIGAN 1993 101961

County Rep.:

APR 28 1995

COMMISSION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

94 DEC 29 AHH: 12

For corners in						
	MONROE		Located In: BEDFORD	Corner Code =##		
	(County)		TWP.	Comer Code		
1.	Public Land Survey		T 9 S R 7 E	A-1		
			T R			
			T R			
_		_	T R			
2	Property Controlling	2	T R		1	

REGISTER OF DEEDS HOWEVE COUNTY, HIGH

_ T ___ in Section . R Miscellaneous S _ R _ Property in Sec. R Т

Register of Deeds Stamp & File Number

4.	Lot No, Recorded Plat						
5.	Private Claims						
	MONROE COUNTY REMONUMENTATION						
	approved corner on 10-26-1993						
Ι,	G.B. WARNKE, JR. in a field survey on	12/13	94				

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points meritioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- G 10 11 12
- A. Description of original monument and accessories and/or subsequent restoration:
 - A-1, T98, R7E, Northwest Township Corner &/or Northwest corner of Section 6 G.L.O. Surveyor Joseph Wampler set post at corner of Township 8 & 9 South, Range 6 & 7 South. Witnesses: B. Oak 18 inch N.45°W. 4 links, B. Oak 11 inch S.31°E. 54 links. / Old book notes stone (Book 14, Page 20), Surveyor unknown, / M.R. Fleck in December of 1946, 1955 & 1973 witnessed stone with R.R. spike above. / Corner has been used by G.B. Warnke & area surveyors as presently monumented by a "T" from leaning over stone and witnessed. / Corner recorded in December of 1975 by Roland Jackson in b.C.R.C., Liber 2, Page 120.
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 - A-1 = 10/36/1993, found 5/8 inch x 9 1/2 inch small engine shaft over stone being approximately 8 inches deep and witnessed as shown below. 12/13/1994, set 1 inch x 36 inch iron pipe with brass remonumentation cap in monument box to replace engine shaft over stone.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

Set 1 inch x 36 inch iron pipe with brass remonumentation cap in monument box to replace A 1 \sim Found 5/8 fuch x 9 1/2 Inch Small Engine Shaft Over Stone Being Approximately 8 Inches Deep and is accepted as a careful and faithful perpetuation of the position of the original corner and witnesses: \$40°W 74.65° northeast corner of foundation of house No. 4301 \$45°% 40.13' found nail/shiner in northeast face of telephone pole

N60°W 60.33' found P.K. nail/shiner in southwest face of telephone pole N15°E 86.09' southwest corner of siding on attached garage at house No. 4298

(previous witness to foundation, now broken)

\$10°E 29.75' found mail/shiner in mortherly face of 30" Oak

N60°E 81.55% found P.K. uail/shiner in southeast face of utility pole

Bigned by __. Date 19474 Burveyor's Michigan License No.

12/13/1994

PDARDED FLAND SURVEYORS, JAN REVISED MAY REVISED MAY 140 REVISED JAN

OF MICHAEL

E OF MONEY

GEORGE B. Wahnke, Ja.

LATER SURVEYOR

3 Plat 502 自設数