

SURVEY & REMONUMENTATION

DEC 07 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD
94 OCT 12 PM 2:46

RATIFIED BY PEER GROUP
PA 345 OF 1990
MONROE COUNTY, MICHIGAN

date: 7-12-94
County Rep.: *[Signature]*

For corners in

MONROE
(County)

Located In:

Corner Code ##

BEDFORD TWP. ON MICHIGAN - OHIO LINE

- 1. Public Land Survey T ___ R ___
T ___ R ___ #5
T ___ R ___
T ___ R ___
- 2. Property Controlling S ___ T ___ R ___
in Section S ___ T ___ R ___
- 3. Miscellaneous S 1 T 9 S R 7 E POST 65
Property in Sec. S ___ T ___ R ___

[Signature]
REGISTER OF DEEDS
MONROE COUNTY, MICH

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

1994 MONROE COUNTY REMONUMENTATION PROGRAM

Peer Group approved corner on 7/12/1994 per Act 345 of 1990.

I, G.B. WARNKE, JR. in a field survey on AUGUST 26, 19 94 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therelore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Post 65 Michigan - Ohio Marker
(East side of Dixie Highway)
1915 Ohio - Michigan boundary survey set granite Post No. 65 on east side of Dixie Highway in Section 1, Town 9 South, Range 7 East. / Post was witnessed by Dean Ringle on 6/11/1992. / Post was witnessed by G.B. Warnke crew on 9/30/1992 before telephone cable was trenched near post. Post was found to be leaning north. Post was re-witnessed after cable installation and post was not disturbed during construction.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Post 65 Michigan - Ohio Marker - 9/30/1992 - Found granite post and witnessed as shown below.
8/26/1994 - rechecked post and witnesses. Post 65 was used in recon. in attempt to locate Post 66.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Post 65 Michigan - Ohio Marker and is accepted as a careful and faithful perpetuation of the position of the original corner and Witnesses:
AZ 270°00'00" 78.52' State of Ohio right-of-way marker on west side of Dixie Highway
AZ 62°53'42" 32.22' southwest corner of foundation - first Michigan residence on east side
AZ 182°29'08" 52.10' northwest corner of foundation at lowest brick at "Alexis Congregational Church"
AZ 106°05'40" 2.91' triangle concrete Fed-aid project marker
AZ 226°24'10" 11.30' Lucas County engineer monument brass cap in concrete

Signed by *[Signature]* Date Aug 26, 1994
Surveyor's Michigan License No. 19474