

**SURVEY &  
MONUMENTATION**

JAN 17 1996

**MONTCALM COUNTY REMONUMENTATION PROGRAM**

**LAND CORNER RECORDATION CERTIFICATE**

**COMMISSION**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Montcalm  
(County)

Located In:

Bloomer Township

Corner Code #

1. Public Land Survey Corner Sec 14 T 9 N R 5 W I-5 Sect
- T. \_\_\_\_\_ R. \_\_\_\_\_  
T. \_\_\_\_\_ R. \_\_\_\_\_  
T. \_\_\_\_\_ R. \_\_\_\_\_
2. Property Controlling in Section S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_  
S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_
3. Miscellaneous Property in Sec. S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_  
S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
MONTCALM COUNTY  
RECORDED

20 DEC 95 11:39 A.M.

VIRGINIA L. KNEPPER  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William Tingley a field survey on June 21, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1831, Orange Risdon, Deputy Surveyor

Set Post Corner to Sections 10, 11, 14 and 15

Beech 10" N25°W 2 links  
Sugar 18" S25°E 83 links

R.D. McNutt, County Surveyor, card file records

E. Youdan 1913, Long Colored Stone

Elm 22" S79°5'W 121-3/4 feet  
Cottonwood 10" N6-3/4°W 149-3/4 feet  
Concrete Fence Post N53°10'W 92 feet

R.D. McNutt, County Surveyor, Bloomer Township Field Book

Stone and stake

Cottonwood Northwest 149-3/4 feet  
Elm Southwest 121-3/4 feet  
Stakes: Southeast 40 feet  
Southwest 35 feet  
Northwest 35 feet

1935, Montcalm County Road Commission Records

Cottonwood N06°W 149.8 feet

Placed Monument Box August 1967

1967 William Downey, R.L.S., Michigan State Highway Department, Survey Chief

Found Boatspike 22" below bituminous pavement; raised with 1/2" pipe; placed monument box.

1977, David B. Whittier, R.L.S. #10070, Survey, Liber 505, Page 154

Monument Box Southwest Corner Section 11

1983, George M. Stevenson, Jr., #13600, Survey Liber 555, Page 971; found 1/2" pipe on Monument Box.

Also Liber 555 page 970 and Liber 555 Page 969

Shows same data

1994, William Tingley, #30104

Iron in Monument Box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" pipe in monument box 6.7 feet North of Centerline Highway M-57 and Centerline of Blackmer Road; directly below found boatspike 1.5 feet long.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Remonumentation Corner over pipe and boatspike in Monument Box.

Set Nail and Tag in Power Pole N45°E 78.48 feet  
Set Nail and Tag in Power Pole N55°W 84.39 feet  
Set Nail and Tag in Power Pole S45°W 72.92 feet  
Northeast Bolt of Restaurant Sign S35°E 88.95 feet


This corner is accepted as a careful and faithful reestablishment of the position of the original corner.

Signed by William Tingley Date 12-12, 1995

Surveyor's Michigan License No. 30104

ACCEPTED BY THE MONTCALM COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 12-12-95

WGT.  
William Tingley, PS, Chairman



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 29, 1971

REVISED MAY 14, 1976

REVISED JAN., 1983

ADAPTED FOR WORD PROCESSING MARCH, 1993