

**SURVEY & REMONUMENTATION**

**FEB 19 1998**

**MONTCALM COUNTY REMONUMENTATION PROGRAM**

**LAND CORNER RECORDATION CERTIFICATE**

**Filing Requirement of Act 74, Mich. P.A. 1970**

**SECTION**

For corners in

Montcalm

(County)

Located In:

Bloomer Township

Corner Code #

- |                                    |        |      |      |                 |
|------------------------------------|--------|------|------|-----------------|
| 1. Public Land Survey              | Sec 11 | T 9N | R 5W | J-3, 1/4 Corner |
|                                    |        | T    | R    |                 |
|                                    |        | T    | R    |                 |
|                                    |        | T    | R    |                 |
| 2. Property Controlling in Section | S      | T    | R    |                 |
|                                    | S      | T    | R    |                 |
| 3. Miscellaneous Property in Sec.  | S      | T    | R    |                 |
|                                    | S      | T    | R    |                 |

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
 MONTCALM COUNTY  
 REGISTERED  
 26 Dec 1997 3:37:01 PM  
 LORI A. WILSON  
 REGISTER OF DEEDS  
 Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William Tingley a field surveyor on July 1, 1996 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1831, Orange Ridson, Deputy Surveyor, GLO Notes  
 39.75 chains set 1/4 Section Post at average distance  
 Black Ash 14" N25°E 4 links  
 Black Ash 18" S54°W 29 links
- 1873, F.A. Palmer, Deputy Surveyor for Montcalm County, Record of Minutes of Survey, Liber 1, page 13  
 Made New Bearing Tree  
 Tree at 1/4 Section Post on South side of Section  
 Black Ash 5" N87-1/2°W 59 links
- 1891, E. H. Jones, County Surveyor, Liber 2, page 12  
 New Bearing Tree South 1/4 Post  
 Elm 16" N85-1/2°W 59 links  
 Elm 7" North 8 links
- R.D. McNutt's county Surveyor, File Card Records  
 Show same bearing trees 1831 through 1891
- 1983 William Ruddell, Surveyor #14769  
 Found Post South 1/4 Section 2
- November 1988, W.G. Tingley #30104, Field Notes Job #88293  
 Set 1/2" Rerod on Fence Corner (North, East and West)  
 Set Nail in 10" Elm N20°E 9.41 feet  
 Set Nail in 8" Elm S85°W 27.85 feet  
 Set Nail in Twin 9" Elm S70°E 30.52 feet  
 Set Nail in 10" Elm S05°W 26.10 feet
- 1988, W.G. Tingley, #30104, LCRC, Liber 2, page 245  
 Set 1/2" Rebar with Identification Cap by single proportioning which fell on occupation fence line.  
 Same bearing trees as above, November 1988

ACCEPTED BY THE MONTCALM COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 5-29-97

WGT  
 William Tingley, PS, Chairman

Continued on back .....

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found cap #30104 on 1/2" Rerod at fence corner North, East and West; position agrees closely with record distances, 2618.88 to Northwest corner and 2636.04 to Northeast corner, from 1891. Measured as 2623.22 and 2639.82 respectively. Also agrees closely with W. Ruddell's 1983 distance of 2641.14 to Northeast Corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- Set remonumentation Corner over rod and cap.
- Nail in 10" Elm N20°E 9.41 feet
  - Nail in 8" Elm S85°W 27.85 feet
  - Nail in 9" Twin Elm S70°E 30.52 feet
  - Nail in 10" Elm S05°W 26.10 feet

This corner is accepted as a careful and faithful re-establishment of the position of the original corner.

Signed by William Tingley Date 5/28/1997

Surveyor's Michigan License No. 30104

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS JAN 28, 1971

