

MONTCALM COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 MONTCALM COUNTY
 RECORDED
 20 DEC 95 11:38 A.M.
 VIRGINIA L. KNEPPER
 REGISTER OF DEEDS

For corners in Montcalm Located In: Bloomer Township Corner Code # _____
 (County)

1. Public Land Survey Sec 1 T 9 N R 5 W M-2, E 1/4
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number


4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, William Tingley a field survey on July 5, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1831, Robert Clark, Jr., Deputy Surveyor, GLO Notes
 1/4 Section Post
 Sugar 24" N68°W 16 links
 Beech 6" S87°W 9 links
1877, R.J. Fraker, Gratiot County Surveyor
 Stone Corner
 Elm 16" N76°W 63 links
 Corner Common to 2 Townships, Section T9N-R5W and Section 6 T9N-R4W

ACCEPTED BY THE MONTCALM COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 12-12-95

 William Tingley, PS, Chairman

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found 2 stones at surface - 1 pointed and slightly larger 0.8 x 0.8 x 1.2 feet. Several smaller stones around and below. At three feet below all stones and under pointed stone, found large stone 0.8 feet x 1.2 feet x 1.2 feet approximately 4 feet West of Centerline Road

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Set Remonumentation Corner in place of pointed stone over larger stone. Left stone beside corner monument.
 Set Nail and Tag 20" Twin Cottonwood N30°W 13.54 feet
 Set Nail and Tag 16" Twin Elm S30°W 34.85 feet
 Set Nail and Tag 12" Elm S45°E 34.23 feet
 Centerline 5" Elm N70°E 21.40 feet

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.



Signed by William Tingley Date 12-12-1995
 Surveyor's Michigan License No. 30104

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1976
 REVISED JAN., 1983
 ADAPTED FOR WORD PROCESSING MARCH, 1993