

SURVEY & REMONUMENTATION

MAY 07 1997

COMMISSION

MONTCALM COUNTY REMONUMENTATION PROGRAM

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
MONTCALM COUNTY
RECORDED

For corners in Montcalm Located In: _____ Corner Code # _____
(County)

12/27/1996 2:08:12 PM

VIRGINIA L. KNEPPER
REGISTER OF DEEDS

- 1. Public Land Survey Sec 36 T 9 N R 6 W
Also known as _____ Sec 31 T 9 N R 5 W
_____ Sec 1 T 8 N R 6 W
_____ Sec 6 T 8 N R 5 W
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

- M-13 SE Corner
- A-13 SW Corner
- M-1 NE Corner
- A-1 NW Corner

Montcalm
Lonia

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William Tingley a field survey on August 19, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

March 10, 1831, Robert Clark, Jr., Deputy Surveyor, GLO Notes

Set Post

White Oak 13" S87°E 24 links

White Oak 16" S64°W 27 links

August 31, 1895, H.M. Caulkin, County Surveyor, page 42

Found reddish stone with crockery under it and rotten stake under it on westside

Took up stone and put down 1-1/2" gas pipe 26" long with stone on westside of it.

October 28, 1994, William G. Tingley, #30401, in Survey #94093

Found 1-1/2" Gas Pipe

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1-1/2" gas pipe and crockery 2.5 feet deep

Found nail Southside Power Pole S80°W 37.13 feet

Found spike Southeast side 6" poplar N40°E 64.41 feet

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Remonument Corner over gas pipe

Roosien iron & cap South 6.06 feet

Found nail southside power pole S80°W 37.13 feet

Found spike Southeast side 6" poplar N40°E 64.41 feet


Southeast corner riser box N55°W 28.20 feet

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William G. Tingley Date 12-23, 1996

Surveyor's Michigan License No. 30104

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1993



ACCEPTED BY THE MONTCALM COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 12-12-95
WGT
William Tingley, PS, Chairman