

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Monument (County)	Located In:	Corner Code //
1. Public Land Survey	T 38 R 7W	D11
	T 36 R 7W	C11
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

**Register of Deeds Stamp & File Number**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

C11 November 02, 1982

I, Gary C. Bielow, in a field survey on D11 November 04, 1982, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

D11: Pine 10 marked as corner in 1837 by US Deputy Surveyor Noah Brookfield. County Surveyor Daoust states "Found stump of pine tree which was U.S. Survey corner. Brove pine root stake with crockery" in 1906. Daoust referenced an Oak 4. S32W. 27 links.  
 C11: Pine 10 marked as corner in 1837 by US Deputy Surveyor Noah Brookfield. County Surveyor Caukin in 1898 reports "put down plow point and mould board" from his memory of relationship of corner to road bed N-S and testimony of Jenks that he helped build the road east and that the center of it was on line. Caukin referenced an Elm 15. N84W. 80-1/2 links. County surveyor Daoust found Caukin's plow point and NBT in 1906 and added witness Pine 6. S6-1/2E. 38 links. Surveyor P White reports setting a 1/2" iron bar for the corner on a 1981 Certificate of Survey recorded in Liber 539, page 35 and witnesses South. 25.83. N41 West side 24' Pine: S70W.59.28. N&T in North side 18" Pine: N85W. 46.85. c/1 3" steel sign post: West. 33.04. 1/2" iron bar.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

D11: Found rotted remains of stake and crockery. Twin 15" and 18" Oak SW matches Daoust's NBT. Accepted remains of stake and crockery as best evidence of original GLO corner location.  
 C11: Found plow point and mouldboard and 1/2" iron bar - plow point is 4' west of bar. 24' Pine south matches Daoust's 1906 NBT. Accepted plow point as best evidence of original GLO corner location.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

D11: Replaced stake and crockery with 1/2"x36" rebar encased in a 4" diameter concrete cylinder capped with a cast aluminum Michigan Department of Natural Resources tablet  
 S34W. 16.79. nail in twin 15" & 18" Oak  
 N4W. 36.56. nail in 14" Oak  
 N44W. 50.07. nail in 14" Oak  
 S71W. 45.34. nail in 10" K Pine

C11: Replaced plow point with 1/2"x36" rebar encased in a 4" diameter concrete cylinder capped with a cast aluminum Michigan Department of Natural Resources tablet  
 S5E. 25.45. spike & tag #12034 in 24" Pine  
 S79W. 55.31. spike & tag #12034 in 20" Pine  
 N81W. 35.45. spike in 12" Basswood  
 S82E. 124.94. spike in 15" W Oak



Signed by *Gary C. Bielow*  
 Surveyor's Michigan License No. 26453

Date 5/4/93

37